

**Design of railway transition zones
A novel energy-based criterion**

Jain, A.; Metrikine, A.V.; Steenbergen, M.J.M.M.; van Dalen, K.N.

DOI

[10.1016/j.trgeo.2024.101223](https://doi.org/10.1016/j.trgeo.2024.101223)

Publication date

2024

Document Version

Final published version

Published in

Transportation Geotechnics

Citation (APA)

Jain, A., Metrikine, A. V., Steenbergen, M. J. M. M., & van Dalen, K. N. (2024). Design of railway transition zones: A novel energy-based criterion. *Transportation Geotechnics*, 46, Article 101223. <https://doi.org/10.1016/j.trgeo.2024.101223>

Important note


To cite this publication, please use the final published version (if applicable). Please check the document version above.

Copyright

Other than for strictly personal use, it is not permitted to download, forward or distribute the text or part of it, without the consent of the author(s) and/or copyright holder(s), unless the work is under an open content license such as Creative Commons.

Takedown policy

Please contact us and provide details if you believe this document breaches copyrights. We will remove access to the work immediately and investigate your claim.



Original Article

Design of railway transition zones: A novel energy-based criterion

A. Jain^{*}, A.V. Metrikine, M.J.M.M. Steenbergen, K.N. van Dalen

Faculty of Civil Engineering and Geosciences (CEG), Department of Engineering Structures, TU Delft, Stevinweg 1, Delft 2628 CN, the Netherlands

ARTICLE INFO

Keywords:

Railway transition zones
Track degradation
Finite element model
Energy analysis
Design criterion
Strain energy

ABSTRACT

Railway transition zones (RTZs) experience higher rates of degradation compared to open tracks, which leads to increased maintenance costs and reduced availability. Despite existing literature on railway track assessment and maintenance, effective design solutions for RTZs are still limited. Therefore, a robust design criterion is required to develop effective solutions. This paper presents a two-step approach for the formulation of a preliminary-design criterion to delay the onset of processes leading to uneven track geometry in RTZs. Firstly, a systematic analysis of each track component in a RTZ is performed by examining spatial and temporal variations in kinematic responses, stresses and energies using a finite element model of an embankment-bridge transition. Secondly, the study proposes an energy-based criterion to be assessed using a model with linear elastic material behavior and states that an amplification in the total train energy in the proximity of the transition interface is an indicator of increased (and thus non-uniform) degradation in RTZs compared to the open tracks. The correlation between the total strain energy (assessed in the model with linear material behaviour) and the permanent irreversible deformations is demonstrated using a model with non-linear elastoplastic material behavior of the ballast layer. In the end, it is claimed that minimising the magnitude of total strain energy will lead to reduced degradation and a uniform distribution of total strain energy in each trackbed layer along the longitudinal direction of the track will ensure uniformity in the track geometry.

1. Introduction

Railway tracks are subject to constant degradation and require frequent maintenance which in turn leads to high maintenance costs and reduced availability of tracks for normal operations. Consequently, a large proportion (40–75%) of railway operating costs are spent on track maintenance [1] to ensure passenger comfort and safety. There is plenty of literature focused on assessment and maintenance of railway tracks. However, the problem at hand still remains and is even intensified in countries with soft soil [2]. The frequency and costs of maintenance in railway transition zones (RTZs) is even higher (4–8 times) compared to the open tracks [1,2]. RTZs are areas where the railway track crosses a structure related to a different transportation modality (bridge, road, culvert, etc.) or where the rail experiences major changes in the type of track support structure. Although there have been several studies [3–7] pointing out the cause of increased degradation in these zones as mainly abrupt change in stiffness and differential settlement, there still is a lack of understanding to design an effective solution to this problem. The current approach to deal with the excessive degradation involves some proactive and reactive measures [6,8–11] that have proved either not as

efficient or even counterproductive in some cases. A robust design solution for RTZs is lacking in literature. RTZs are built similarly to regular railway tracks with some modifications addressing the stiffness jump and differential settlement but without a complete knowledge of the variation of dynamic response of each track component. In order to delay the onset of processes leading to uneven track geometry due to non-recoverable permanent deformations in RTZs, there is a need for an effective design solution. The formulation of an effective design solution demands mainly two steps as discussed below.

Firstly, there is a need to perform a systematic analysis of each track component in RTZs which involves a detailed study of spatial and temporal variation of kinematic responses, stresses and energies. A railway track is composed of several components and each component serves a specific function in the system. The response of each track component experiences a variation in vertical (depth of the track), transversal (along the width of the track), and longitudinal (along the length of the track) directions. These variations affect the performance of the track components in the track which in turn drives non-uniform degradation and the failure process. In addition to this, the degradation or failure of one component has an effect on the performance of the

^{*} Corresponding author.

E-mail address: A.jain-1@tudelft.nl (A. Jain).

other components in the track system. Therefore, the damage prediction requires a detailed and systematic study of the behavior of each track component and an in depth understanding of interactions between components. The current literature [10,12–21] focuses either on any particular track component (mostly rail, sleepers or ballast) or on one particular track response (mainly vertical displacements or accelerations or stress in ballast layer). However, a detailed analysis of the spatial and temporal variation of the response of each track component in RTZs is lacking in the literature. Furthermore, an energy analysis of the track components in RTZs, which could help identify signs of degradation, has not yet been presented in the existing literature. The significance of energy variation will be discussed in the following paragraph, and this paper will investigate it in detail.

Secondly, the identification of an appropriate design criterion affecting the response of RTZs is essential to design an effective design solution. The current literature evaluates the performance of a RTZ mainly by assessing either permanent vertical track deformations or stresses in the ballast layer. However, the question can be asked whether the deformations or the stresses at this particular interface are sufficient to describe the onset of degradation in a RTZ. What precisely leads to faster degradation of these zones compared to the open tracks? The source, spacial extent and location of the degradation in these zones are still unknown. As indicated above, the literature lacks an insight into the spatial and temporal distribution of kinetic and potential energies in railway track components, while this is an indispensable information to answer the question posed. Studies conducted by different authors [22–24] have pointed out that both elastic and inelastic strain energy can be associated with material degradation and may aid in identifying potential failure mechanisms. In [22] authors have studied shakedown of soil in different test setups in terms of elastic and plastic strain energies. In [25] authors assessed the susceptibility of railway tracks to degradation by quantifying the mechanical energy dissipated under a moving train axle, but, due to its dimensional constraints, the model could neither demonstrate the variations of these energies in each layer of the substructure nor was focused on railway transition zones. Hence, the current work will investigate the mechanical energy distribution in space and time for RTZs using a model with linear elastic materials and demonstrate a correlation of the predicted responses with irreversible permanent deformation leading to uneven track geometry. In the end, this work will propose a strain-energy-based design criterion to minimize the degradation in RTZs.

This work is mainly divided into two parts addressing the points mentioned above. In the first part of this work, a 2-dimensional (2-D) model of an embankment bridge transition with linear elastic materials is used to study the spatial and temporal distribution of the kinematic responses, stresses and energies for various track components. As the intent of this paper is to identify a possible design criterion for transition zones, the focus is not so much on the absolute values of the responses under study but on their variation in space and time; the 2-D model suffices for that purpose. The computational objective of the model used in the first part of the paper is to study the amplification in the above-mentioned responses of the track components in the approach zone (proximity of the transition interface) compared to the open tracks (far from the transition interface). In the second part of this work, the design criterion is proposed by evaluating the results obtained in the first part of the paper. Moreover, the validity of the proposed strain-energy-based criterion is demonstrated using another model with non-linear elastoplastic material. The only difference in the models used in the first (linear elastic materials) and the second (non-linear elastic material) parts of the paper is the material for the ballast layer. All models used in this paper are identical in geometry and loading conditions. Finally, it is to be noted that the proposed criterion only covers operation-driven permanent deformations resulting from dynamic amplifications and/or non-uniformity in the responses, and hence, autonomous settlements are not included in the paper.

2. Methods

In this paper, an embankment-bridge transition is studied which consists of ballasted track and a concrete bridge. The ballasted track ("soft side") consists of track components namely rail, rail-pads, sleepers, ballast, embankment and sub-grade underneath. The ballast-less track ("stiff side") consists of rails connected to sleepers (with under sleeper pads) resting on the concrete bridge.

2.1. Geometric model

The geometric model is 80 m (132 sleepers) long which consists of 60 m of ballasted track and 20 m of ballast-less track (concrete bridge). For this study, the geometrical model is divided into four zones (see Table-1) with additional 20 m at the beginning and 10 m at the end in order to eliminate the influence of boundaries (left and right extremes) on the results for the reasons discussed in Section 2.2. Fig. 1 shows the approach zones (AZ) on both sides that together constitute the transition zone (TZ), and open track (OT) on both sides are the zones that are practically free from any transition effects. In addition to this, Fig. 1 shows materials (steel, concrete, ballast, sand, clay) of the track components in the legend and a magnified (scale 2:1) cross-section (section A) of the embankment-bridge transition under study with the depths of the trackbed layers (ballast, embankment and subgrade) marked in red. The length of each zone under study (OT-I, OT-II, AZ-I and AZ-II) is also marked in Fig. 1.

The geometric model mainly consists of following track components (Fig. 1):

- Rail: rail profile 54E1 (UIC54) manufactured according European Standard EN 13674–1
- Rail-pads: connecting rails to sleepers
- Sleepers: 240 mm x 240 mm, concrete
- Ballast: 0.3 m deep layer of ballast
- Embankment: 1 m deep dense sand under the ballast
- Natural terrain or subgrade: clayey soil of 1 m depth
- Under Sleeper pads (USPs) [26]: under sleeper pads of 0.01 m thickness under the sleepers on the stiff side
- Bridge: concrete bridge with fixed bottom of length 20 m

The sleeper spacing adopted is 0.6 m and the first sleeper next to the transition is located at 0.3 m from the interface of ballasted and ballastless track.

2.2. Numerical Model

A 2-D Finite Element (FE) model was created using ABAQUS, with geometrical details mentioned in the previous section. The railway track components and the bridge were modelled using four-node plane-strain elements and the rail was modelled as a beam. Rayleigh damping (as suggested in [27]) for materials (see Table-2) was used to incorporate realistic energy dissipation in the system. The length and depth of the model were chosen such that there is hardly any influence of the wave reflections from the boundaries (extreme right, left and bottom of the system) on results of the zones under study while restricting the vertical displacements to maintain a reasonable value as per literature [28,29]. The depth of the layers under the sleepers was sufficient to reduce

Table 1
Details of the zones under study.

Zones	Length [m]	Description
OT-I	20	open track-soft side
AZ-I	20	approach zone-soft side
AZ-II	5	approach zone-stiff side
OT-II	5	open track-stiff side




Fig. 1. Cross-sectional details of the embankment-bridge transition and the division of zones (OT-I, AZ-I, AZ-II, OT-II) under study.

Table 2

Mechanical properties of the track components.

Material	Elasticity Modulus	Density	Poisson's Ratio	Rayleigh damping	
	E [MN/m ²]	ρ [kg/m ³]	ν	α	β
Steel (rail)	210000	7850	0.3	–	–
Concrete (sleepers)	35000	2400	0.15	–	–
Ballast	150	1560	0.2	0.0439	0.0091
Sand (embankment)	80	1810	0.3	8.52	0.0004
Clay (subgrade)	25.5	1730	0.3	8.52	0.0029

dynamic stresses at the bottom of the subgrade to less than 3% (this value was suggested to be less than 10% in [28] so as to eliminate artificial boundary effects) of their values at the bottom of the sleepers. The following subsections describe the details regarding the numerical model used for FE analysis in terms of mesh properties, mechanical properties of materials, interactions between the track components, loads, constraints, boundary conditions and analysis procedures.

2.2.1. Mesh

The sleeper, ballast, embankment, subgrade and the bridge were discretized [30] using linear quadrilateral elements of type CPE4R (12424 elements) and rail using two-node linear line elements of type B21 (7860 elements) to form a very regular mesh. The most critical zone (AZ-I) under study was meshed finer than rest of the model in order to obtain accurate results.

2.2.2. Mechanical properties

The materials used for all track components are characterised by elastic properties (Young's modulus, Poisson's ratio), densities and Rayleigh damping factors [31,32,27,33]. A static analysis was performed in order to tune the elasticity (Young's modulus) of the USP on the stiff side such that the static vertical displacements on soft and stiff sides are the same. The details of these parameters are mentioned in Table-2.

2.2.3. Interface and boundary conditions

The following key interface and boundary conditions were chosen with no separation allowed at any interface:

- Rail-sleeper: Rail was connected to the midpoints of the sleeper edges via railpads represented by vertical springs ($k = 1.2 \times 10^8$ N/m) and dashpots ($c = 5 \times 10^4$ N-s/m) [33].
- Sleeper-ballast, ballast-embankment, embankment-subgrade: surface-to-surface tie constraint (perfect matching of displacements and forces) was used for defining the conditions at these three interfaces.
- Vertical interface between ballast/ embankment/ subgrade and concrete bridge: a hard contact linear penalty method was used to define the normal behaviour and Coulomb's friction law was

adopted to define the tangential behaviour with a frictional coefficient equal to 0.5. (details can be found in [30])

- The bottom of the subgrade and the bridge were fixed.

The simulation was performed in two steps. Firstly a static step was performed to consider the effects of gravity in order to obtain the initial stress state of the model under self-weight. It was followed by a dynamic analysis (full Newton-Raphson method) for 1.75 s with a time step of 0.005 s. The loads that have been considered are: gravity load for static analysis and one moving axle load of 90 kN with velocity of 144 km/hr for dynamic analysis. The load moving in the direction from soft side to stiff side of the transition was simulated using the DLOAD subroutine in ABAQUS [30,34]. Note that the formulation of a design criterion, which is the ultimate objective of this paper, is not qualitatively influenced by the specific character of the moving load. Therefore, the simplest loading conditions have been adopted in this work as the main objective is to "formulate" a design criterion by comparing the responses of the track components in the approach zones to the open tracks and capturing the main mechanisms governing the dynamic amplifications in RTZs in the cleanest possible manner. The amplification of dynamic responses in the approach zone is expected to be higher for higher speeds and axle loads. Therefore, the designers must perform a sensitivity analysis for different vehicle characteristics (speeds, axle loads etc.) to achieve the most effective "use" of the proposed design criterion.

3. Results and Discussion

In this section, the results are presented in two parts. Firstly a systematic analysis of the track components is performed by studying the kinematic responses (displacement, velocity and acceleration) of rail, sleepers and ballast, forces in rail pads, and maximum equivalent Von Mises stress at top and at the bottom of sleepers, ballast, embankment and subgrade (for a region of 0.6 m under each sleeper). The kinetic energy (KE) and strain energy (SE) variation in space and time is studied for the track bed layers (ballast, embankment and subgrade). Secondly, the analysis mentioned above is used to present a design criterion for RTZs, and its correlation with permanent deformations is demonstrated by comparing results of the analysis with linear elastic material to the one with a non-linear elastoplastic material behaviour of the ballast. It is

to be noted that the discussion in this section related to the percentage increase of any of the responses (X) studied in this paper are calculated using the equation below:

$$\text{Percentage increase} = \frac{(X_{AZ} - X_{OT}) \cdot 100}{X_{OT}} \quad (1)$$

where X_{AZ} and X_{OT} are any of the responses under study (displacement, velocity, acceleration, stress, kinetic energy, strain energy) in the approach zone and open track respectively.

3.1. Analysis of RTZs

3.1.1. Kinematics of transition zones

Rail: Fig. 2 shows time history of displacement, velocity and acceleration for 10 control points each in AZ-I and AZ-II. The responses of the rail nodes above the sleepers on both sides right next to the transition show an increase when compared to nodes far from the transition. On one hand the increase in the maximum displacement under the load is only 5.4%, which can be attributed to the fact that only one axle is being studied. On the other hand, the increase in velocity (20%) and acceleration (15.5%) is much larger. Also, some permanent deformation can be seen (based on the final non-zero value of the displacements in Fig. 2 and Fig. 3 at time moment $t = 1.7$ s) at locations (e.g., at sleeper 1) close to transition enabled by frictional sliding at the transition interface.

Sleepers: Fig. 3 shows time history of displacement and accelerations for 10 control points each (midpoint of sleeper top and bottom) in AZ-I

and AZ-II. It can be noticed that 0.114 mm of permanent deformation occurs at sleeper number 1 which can be again attributed to frictional sliding at the transition interface. Although the variation of the kinematic response from top to bottom of the sleepers is negligible, there is a significant increase in the displacements (9.5%) and accelerations (37.3%) of the sleepers on left (sleeper 1) and right (sleeper -1) of the transition interface when compared to the sleepers (10, -10, respectively) in far field.

Ballast: The authors in [35] have associated breakage of ballast particle corners to load frequencies between 10–20 Hz, densification or compaction of ballast without much breakage was associated to load frequencies of 20–30 Hz and all load frequencies above 30 Hz can be associated with splitting of particles. Hence, the amplitude spectra of accelerations for ballast at different locations (under sleepers 1, 2, 10) are analyzed. A significant amplification (38.3%) is observed in the ballast acceleration under sleeper 1 (0.54 g) compared to the ballast acceleration (0.39 g) under sleeper 10. It can be clearly inferred from Fig. 4 that the ballast in the approach zone (under the sleeper 1) is more susceptible to phenomena of corner breakage, compaction and splitting of particles compared to ballast in open tracks, which is in line with what has been observed in reality [36].

Clearly, the results in Fig. 2 and Fig. 3 show an increase in kinematic quantities at the locations of the first sleeper in AZ-I and AZ-II when compared to the open track on both sides. This is in agreement with the current literature [36,37,32] but site measurements show that the first three sleepers (in AZ-I) next to the transition interface are critical in




Fig. 2. Time history of displacement, velocity and acceleration for 10 control points (on each side of transition interface) of the rail (above sleepers). The dashed lines show the time moments at which the moving load leaves the AZ-I and AZ-II. The red (soft side) and blue lines (stiff side) are the results for the control points above the first sleeper next to transition interface on both sides.




Fig. 3. Time history of displacement and acceleration for 10 control points (on each side of transition interface) on top (solid lines) and bottom (dashed lines) of the sleepers. The dash-dotted lines show the time moments at which the moving load leaves the AZ-I and AZ-II. The red (soft side) and blue lines (stiff side) are the results for the first sleeper next to transition interface on both sides.




Fig. 4. Time history of accelerations(left) and the amplitude spectra of accelerations (right) for two point on top of ballast layer under sleeper 1, 2 and 10.




Fig. 5. Time history of vertical forces in 10 rail-pads next to transition interface on each side. The red lines show the forces in first two rail-pads on the soft side and the blue line shows the force on first sleeper on the stiff side of the transition interface.

terms of observed damage. This shows that only kinematic studies are not adequate to predict damage in RTZs and for that reason we further investigate forces/ stresses and energies in the following sections.

3.1.2. Stresses and forces in transition zones

Rail-sleeper interaction forces: Fig. 5 shows a 5% increase in force (compressive) for the rail-pad connecting sleeper 2 to the rail compared to the force for rail-pad connecting sleeper 10 (in the open track) to the

rail. Moreover, the rail-pad connecting sleeper 1 to the rail experiences a tensile force (with respect to the prestress in railpads which is typically present in practice) of approximately 4 kN. In the model, this is due to AZ-I and AZ-II deforming differently, which results in sleeper 1 hanging on the rail. In reality there might be a tensile force or reduction in prestress based on the conditions present at the site.

Maximum equivalent Von Mises stress: In this section the maximum equivalent Von Mises stresses at the top and bottom of each track component (sleepers, ballast, embankment, subgrade) are assessed in terms of their variation along the longitudinal direction (i.e., 'n' denotes the sleeper number). According to the Von Mises criterion, yielding of a material begins when the equivalent Von Mises stress exceeds the yield stress of the material. It is to be noted that the observed magnitude of the Von Mises stresses (Fig. 6) is not close to the yield stresses of the materials as the system is studied only for one axle load. However, the stress amplification in the AZ-I compared to OT-I can be clearly seen in Fig. 6. This implies that AZ-I will yield earlier than OT-I. The stress amplifications are observed under the first three sleepers.

Fig. 6 shows that the max. Von Mises stresses under the sleepers 4–10 are the same while there is an amplification under sleepers 1, 2 and 3 (similar to situation on top of the sleepers), which might lead to differential settlement in the long term. Also, a spike in stress can be seen on sleeper 2 and on the ballast under sleeper 2, which is consistent with the amplification in rail-pad force at this particular location (Fig. 5). Moreover, the non-uniformity in max. Von Mises stress under sleepers 1, 2 and 3 for embankment and subgrade can be due to a combination of increased force in the rail-pad connecting sleeper 2 (Fig. 5) to the rail and the boundary effects (reflection) at the transition interface. An amplification in max. Von Mises stress (Fig. 6) in AZ-I compared to OT-I is clearly seen but minimizing these stress values does not necessarily assure that the materials do not fail at lower stresses. This is due to the fact that the Von-Mises criterion is essentially an energy criterion which only covers the maximum distortional energy density (it is proportional to the square of the maximum Von-Mises stress) expressed as follows:

$$U_d = \frac{1 + \nu}{3E} \sigma_{VM}^2 \quad (2)$$

where ν is Poisson's ratio, E is Young's modulus, σ_{VM} is the equivalent Von-Mises stress, and U_d is distortional energy density. The maximum distortion energy theory (Von Mises yield criterion) proposes that the total strain energy can be separated into two components: the volumetric strain energy and the distortional strain energy; failure is said to occur when the distortional component reaches the critical value. However, this criterion is most suitable for predicting the yielding conditions of metals and alloys. In RTZs the volumetric strain energy will also play a considerable role in phenomena like breakage, compaction and splitting of ballast particles, eventually resulting in a non-uniform transverse and longitudinal profile of the ballast layer. Although prediction of the type of failure is beyond the scope of this work, it is important to study the total strain energy (as used by authors in [22] to study the failure of soils) in order to assess the degradation in RTZs.

As shown in this section, the percentage increase in max. Von Mises stress for the layer of ballast in AZ-I compared to OT-I is 2.57% and the percentage increase in corresponding distortional energy is 5.2%. In the following sections, an increase in the total energy will be studied in terms of spatial and temporal variation and the percentage increase will be compared with that of Von Mises stress and distortional energy.

3.1.3. Energy variation in transition zones

Kinetic energy: Fig. 7 shows the spatial variation of the kinetic energy (plotted for each element with maximum at marked time moments) in ballast (a) embankment (b) and subgrade (c) in the AZ-I at 5 different time instances marked in the figure where a peak (t_2, t_4) or dip (t_3) can be seen in the total kinetic energy and a time instant where the energy is nearly constant (t_1). The colours shown in Fig. 7 are associated with the values shown in the legend, where blue represents the lowest magnitude and red represents the highest magnitude of kinetic energy. The time instances t_2 and t_4 , when the total kinetic energy has significantly increased, correspond to the load positions above the second sleeper on both sides of the transition interface. It is also interesting to observe that the increase of kinetic energy in the ballast layer is distributed all over the depth (Fig. 7a for time instance t_2 and t_4) in the proximity of the transition interface. On the contrary, this increase is localized for the







Fig. 6. Maximum equivalent Von Mises stress at top (red) and bottom (blue) of (a) sleepers, (b) ballast, (c) embankment, and (d) subgrade for one sleeper bay.



(a)



(b)



(c)

Fig. 7. Spatial distribution of kinetic energy per unit depth in AZ-I in (a) ballast (b) embankment (c) subgrade at time instances t_{1-3} . The graphs show the time moments (dashed lines) at which the load enters/exits the AZ-I and the time interval (grey shaded region) for which the load stays in the AZ-I.

layers of embankment and soil in the top corner of these layers (also close to the transition interface); see Fig. 7b and c. This concludes that the kinetic energy has more significant effect in the ballast layer compared to embankment and subgrade, which could be related to high wear of the ballast particles. Also, it is worth noticing that the elements next to the transition interface experience an increase in kinetic energy even after the load has left.

Fig. 8 shows the temporal variation of the kinetic energy per unit depth in each track component (ballast, embankment, subgrade) in all the zones under study (OT-I, AZ-I, AZ-II, OT-II). The dash-dotted lines in the graphs show the time moments at which the load enters and exits the OT-I, AZ-I, AZ-II, OT-II. The total kinetic energy density decreases (approximately 5 times) in magnitude as we investigate deeper in the system whereas the total kinetic energy on soft side is approximately







Fig. 8. Temporal variation of total kinetic energy per unit depth in ballast, embankment and subgrade for each zone (OT-I, AZ-I, AZ-II, OT-II).



(a)



(b)



(c)

Fig. 9. Spatial distribution of strain energy per unit depth in AZ-I in (a) ballast (b) embankment (c) subgrade at time instances t_{1-3} . The graphs show the time moments (dashed lines) at which the load enters/exits the AZ-I and the time interval (grey shaded region) for which the load stays in the AZ-I.

100 times higher than that on the stiff side.

Strain energy: Fig. 9 shows a spatial variation of strain energy (plotted for each element with maximum at marked time moments) in ballast (a) embankment (b) and subgrade (c) in the AZ-I at 3 different time instances marked in the figure where extremes (t_2, t_3) can be seen in the total strain energy in ballast layer and a time instant where the strain energy is constant (t_1). However, these critical time moments at which the strain energy curve exhibits extremes correspond to different load positions. In the ballast layer, the maximum total strain energy peak occurs at t_3 , which is the time moment at which the load crosses the third sleeper (soft side). Similarly, a sharp local increase of strain energy can be seen at the bottom of the embankment layer (Fig. 9b) at the time instance when the load passes over the second sleeper (soft side). In addition to this, a similar increase can be seen for the subgrade at the time moment when the load crosses the first sleeper (soft side). This shows correspondence to results obtained from both kinematic and stress studies combined together. Moreover, the locations of the strain energy peaks are restricted to regions next to the transition interface (for ballast) and the interfaces between the three track bed layers.

Fig. 10 shows the temporal variation of the total strain energy (contribution only due to dynamic components) per unit depth in each track component (ballast, embankment, subgrade) in all the zones under study (OT-I, AZ-I, AZ-II, OT-II). The dash-dotted lines in the graphs show the time moments at which the load enters and exits the OT-I, AZ-I, AZ-II, OT-II. The total strain energy density increases (approximately 2.5 times) in magnitude as we investigate deeper in the system whereas the total strain energy on soft side is approximately 300 times larger than that on the stiff side.

3.2. Design criterion

A design criterion for RTZs can be proposed based on the comprehensive analysis presented in the first part of this work.

In the first phase of analysis in Section 3.1.1, the kinematic study suggested that there is a significant increase in displacements (5.4% to 9.5%) and accelerations (15.5% to 38.3%) for the track components (rail, sleepers and ballast) in the transition zone compared to open tracks. The location of the peak value of the kinematic responses under study for each of these track components was in the regions around the first sleeper on either side of the transition interface. The critical values of kinematic response occurred at the time moment when the load was passing over the location where the peak response was observed. In summary, a significant amplification in kinematic response was observed for each track component but it was localized to the region around the first sleeper only. Even though a kinematic response provide valuable information regarding dynamic amplifications in transition zones, it cannot be used as a valid design criterion to reduce degradation as site measurements [36,37,32,38] suggest that the degradation in RTZs is observed at locations around the first 3 sleepers next to the transition interface. Therefore, the kinematic response can be a good criterion to evaluate the performance of the upper track components namely rail and sleepers but is insufficient to describe the degradation

processes in the lower trackbed layers.

The second phase of analysis in Section 3.1.2 shows that there is a significant increase in max. equivalent Von Mises stress for each of the track components namely sleepers, ballast, embankment and subgrade in AZ-I compared to the OT-I. The location of the maximum Von Mises stress values for the ballast layer was under the second sleeper next to the transition interface on the soft side of the track. The peak value of the Von Mises stress in embankment layer was localized to the transition interface while in the subgrade layer the peak was in the region around the third sleeper (soft side) next to the transition interface. On one hand, the max. equivalent Von Mises stress shows that the critical locations are similar to those observed on many sites [36,37,32,39,38]. However, on the other hand, based on the discussions above (see Section 3.1.2), the Von Mises criterion takes into account only the distortional component of strain energy and cannot explain all degradation mechanisms that are expected to occur in RTZs. Therefore, to assess or alleviate degradation mechanisms in RTZs, it is more comprehensive to consider the total strain energy, which comprises both distortional and volumetric components. Fig. 11 summarises the comparison of percentage increase in max. Von Mises stress, distortional energy and total strain energy for the layer of ballast in AZ-I relative to the OT-I. Clearly, the total strain energy is significantly larger than the distortional energy.

The third phase of analysis in Section 3.1.3 was focused on the spatial and temporal variation of the mechanical energy. It can be clearly seen from Fig. 7 and Fig. 9 that both the total kinetic and strain energies increase by a significant amount for the top track-bed layer (ballast) in AZ-I compared to OT-I. This increase is less prominent in the lower layers (embankment and subgrade). The location of peak values of the energy is in the region around the first to the third sleeper on the soft side of the transition interface. The time moments at which these peak values are observed are when the load passes above sleeper 1 (for ballast), sleeper 2 (for embankment) and sleeper 3 (for subgrade). This shows that energy combines the information obtained from both kinematics and stresses and is therefore a more comprehensive quantity. Now that the magnitude of total kinetic energy is negligible compared to the total strain energy, the authors claim that the degradation of RTZs can be reduced by minimizing the increase in total strain energy in track-bed layers. It is to be noted that the increase in total strain energy for each track-bed layer will depend on various factors such as soil type, degree of compaction of the materials, magnitude and velocity of the




Fig. 11. Comparison of percentage increase in Von Mises stress, distortional energy and total strain energy for the ballast layer in AZ-I relative to OT-I.




Fig. 10. Temporal variation of total strain energy per unit depth in each track component for each zone (OT-I, AZ-I, AZ-II, OT-II).

load etc. This study shows a significant increase only in the ballast layer due to the choice of model and material parameters, but each layer should be monitored for any increase in total strain energy in the proximity of the transition interface.

Based on the above discussions and results shown in Section 3.1.3, it has been claimed that the total strain energy can be seen an indicator of potential damage in RTZs. In reality, a fraction of this total strain energy is recoverable (elastic) and the rest is dissipated through damage. This leads us to the conclusion that in order to minimise the degradation in RTZs, it is evident that there is a need to minimise the total strain energy in each of the track-bed layers. Moreover, a uniform distribution of the total strain energy along the longitudinal direction of track will ensure that there is no non-uniformity in degradation due to localised amplifications in the proximity of a transition interface. The validity of the proposed criterion can be demonstrated by establishing a correlation between permanent irreversible deformation (obtained from model 2) and total strain energy (obtained from model 1). This is done by comparing the results obtained from model 1, which includes linear elastic behaviour of the materials, and model 2, which includes a non-linear elastoplastic behaviour of the material representing the layer of ballast. The material model [40,41], the stress-strain relationship and the damage parameters [42] used for simulating the non-linear elastoplastic material (model 2) comparable to ballast are adopted from literature and are used only for demonstration purposes. Hence, the authors do not claim that the absolute values of the quantities shown are fully representative of the railway track materials.

Fig. 12 shows the permanent deformation observed at rail level above each sleeper (a) and the variation of the total strain energy for the layer of ballast (b) in OT-I and AZ-I for both linear elastic (model 1) and non-linear elastoplastic (model 2) material behaviour. It is to be noted that the rail deformation shown in Fig. 12a is non-zero at all locations because of the static load due to gravity being active at all time moments. As for Fig. 12, the total strain energy (for a finite volume) comprises solely recoverable strain energy for model 1, while for model 2, it accounts for both recoverable and dissipated strain energy resulting from damage. This explains the increasing trend of the total strain energy (in model 2) with the moving load progressing in the given volume.

The dashed lines in Fig. 12b represent the time moments at which the load enters and leaves OT-I and AZ-I. The locations of the strain-energy peaks (in AZ-I) predicted by both models are clearly the same, which shows the potential of model 1 to indicate damage. The increase in peak value of the total strain energy in AZ-I with respect to OT-I for model 1 is 1.28 J, and for model 2 is 0.57 J. This difference in the values is related to the non-linear material (model 2) undergoing permanent deformation (Fig. 12a) in AZ-I, which is also reflected in the final strain energy difference (0.48 J) between OT-I and AZ-I, as seen in Fig. 12b. In conclusion, the findings (Fig. 12) indicate that the total strain energy peak observed in the model with linear elastic material behavior is associated with a localized increase (compared to open track) in irreversible deformation in the vicinity of the transition interface (under sleepers 1, 2, 3; see Fig. 12a) in the model with non-linear elastoplastic material. This demonstrates the validity of the design criterion proposed in this section.

It is to be noted that even though this paper proposes an energy-based criterion for the preliminary design of railway transition zones, the application is not limited to only design purposes [43,44]. The proposed energy-based criterion can be used to evaluate the on-site condition (indicative) of a railway track or a transition zone by computing energy flux based on measured quantities (stress, strain etc.) that characterize the kinematic and dynamic responses of the system at critical points. However, in order to achieve full accuracy in the evaluation of the on-site condition using any approach (energy-based or other classical methods), detailed numerical models (tuned using measured data at monitoring points) must be used to predict the system's service situation.

4. Conclusions

In the first part of this paper, a systematic and detailed analysis of an embankment-bridge transition was conducted where the spatial and temporal distribution of displacements, velocities, accelerations, forces, stresses and mechanical energy were thoroughly studied for the main track components. The investigation resulted in mapping the location and extent of the transition effects and formed the basis for the




Fig. 12. Comparison of (a) rail deformation and (b) total strain energy obtained from the model with linear elastic material behaviour (model 1) and non-linear elasto-plastic material behaviour (model 2) of ballast in RTZs for OT-I and AZ-I.

formulation of an energy-based design criterion that can be used in preliminary design to mitigate the amplified degradation of RTZs. The second part of the paper proposes the total strain energy based on a model with linear elastic materials as an indicator to predict degradation. The validity of this proposal was demonstrated and a clear correlation was found between the peak in the total strain energy (in the model with linear elastic material behaviour) and the localised increase in irreversible deformation (in a model with non-linear elastoplastic material behaviour) in the proximity of the transition interface. Therefore, it is concluded that the degradation in railway transition zones can be reduced by minimising the total strain energy in each track-bed layer in the approach zone or to the very least minimising the amplification and non-uniformity of the total strain energy in approach zones relative to the open track. It is claimed that minimising the magnitude of total strain energy will imply lesser permanent deformation and hence reduced degradation, and a uniform distribution of total strain energy along the longitudinal direction of the track will imply uniform degradation.

Declaration of Competing Interest

The authors declare that they have no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

Data availability

Data will be made available on request.

Acknowledgements

This research is supported by the Dutch Technology Foundation TTW (Project 15968), a part of the Netherlands Organisation for Scientific Research (NWO), and which is partly funded by the Ministry of Economic Affairs.

References

- Coelho B, Hölscher P, Priest J, Powrie W, Barends F. An assessment of transition zone performance. *Proc Inst Mech Eng, Part F: J Rail Rapid Transit* 2011;225(2): 129–39. <https://doi.org/10.1177/09544097jrrt389>.
- Varandas JN, Hölscher P, Silva MA. Dynamic behaviour of railway tracks on transition zones. *Comput Struct* 2011;89(13–14):1468–79. <https://doi.org/10.1016/j.compstruc.2011.02.013>.
- Nielsen JC, Berggren EG, Hammar A, Jansson F, Bolmsvik R. Degradation of railway track geometry – correlation between track stiffness gradient and differential settlement. *Proc Inst Mech Eng, Part F: J Rail Rapid Transit* 2018;234(1):108–19. <https://doi.org/10.1177/0954409718819581>.
- Indraratna B, Sajjad MB, Ngo T, Correia AG, Kelly R. Improved performance of ballasted tracks at transition zones: A review of experimental and modelling approaches. *Transport Geotech* 2019;21:100260. <https://doi.org/10.1016/j.trgeo.2019.100260>.
- Sañudo R, dell'Olio L, Casado J, Carrascal I, Diego S. Track transitions in railways: A review. *Constr Build Mater* 2016;112:140–57. <https://doi.org/10.1016/j.conbuildmat.2016.02.084>.
- Transportation Research Board and National Academies of Sciences, Engineering, and Medicine, Design of Track Transitions, The National Academies Press, Washington, DC, 2006. doi:10.17226/23228.
- Li D, Davis D. Transition of railroad bridge approaches. *J Geotech Geoenviron Eng* 2005;131(11):1392–8.
- Ribeiro CA, Paixão A, Fortunato E, Calçada R. Under sleeper pads in transition zones at railway underpasses: numerical modelling and experimental validation. *Struct Infrastruct Eng* 2014;11(11):1432–49. <https://doi.org/10.1080/15732479.2014.970203>.
- Paixão A, Fortunato E, Calçada R. Transition zones to railway bridges: Track measurements and numerical modelling. *Eng Struct* 2014;80:435–43. <https://doi.org/10.1016/j.engstruct.2014.09.024>.
- Paixão A, Fortunato E, Calçada R. A numerical study on the influence of backfill settlements in the train/track interaction at transition zones to railway bridges. *Proc Inst Mech Eng, Part F: J Rail Rapid Transit* 2015;230(3):866–78. <https://doi.org/10.1177/0954409715573289>.
- Wang H, Markine V. Corrective countermeasure for track transition zones in railways: Adjustable fastener. *Eng Struct* 2018;169:1–14. <https://doi.org/10.1016/j.engstruct.2018.05.004>.
- M. Shahraki, K.J. Witt, 3d modeling of transition zone between ballasted and ballastless high-speed railway track, *Journal of Traffic and Transportation Engineering* 3 (4). doi:10.17265/2328-2142/2015.04.005. URL: <https://doi.org/10.17265/2328-2142/2015.04.005>.
- Wang H, Silvest M, Markine V, Wiljanen B. Analysis of the dynamic wheel loads in railway transition zones considering the moisture condition of the ballast and subballast. *Appl Sci* 2017;7(12):1208. <https://doi.org/10.3390/app7121208>.
- Insa R, Salvador P, Inarejos J, Roda A. Analysis of the influence of under sleeper pads on the railway vehicle/track dynamic interaction in transition zones. *Proc Inst Mech Eng, Part F: J Rail Rapid Transit* 2011;226(4):409–20. <https://doi.org/10.1177/0954409711430174>.
- Banimahd M, Woodward PK, Kennedy J, Medero GM. Behaviour of train-track interaction in stiffness transitions. *Proc Inst Civil Eng - Transport* 2012;165(3): 205–14. <https://doi.org/10.1680/tran.10.00030>.
- Real-Herráiz J, Zamorano-Martín C, Real-Herráiz T, Morales-Ivorra S. New transition wedge design composed by prefabricated reinforced concrete slabs. *Latin Am J Solids Struct* 2016;13(8):1431–49. <https://doi.org/10.1590/1679-78252556>.
- Paixão A, Ribeiro CA, Pinto N, Fortunato E, Calçada R. On the use of under sleeper pads in transition zones at railway underpasses: experimental field testing. *Structure and Infrastructure Engineering* 2014;11(2):112–28. <https://doi.org/10.1080/15732479.2013.850730>.
- Ribeiro CA, Paixão A, Fortunato E, Calçada R. Under sleeper pads in transition zones at railway underpasses: numerical modelling and experimental validation. *Struct Infrastruct Eng* 2014;11(11):1432–49.
- Varandas J, Hölscher P, Silva M. Three-dimensional track-ballast interaction model for the study of a culvert transition. *Soil Dynam Earthquake Eng* 2016;89:116–27. <https://doi.org/10.1016/j.soildyn.2016.07.013>.
- Sayed MA, Shahin MA. Design of ballasted railway track foundations using numerical modelling. part i: Development. *Can Geotech J* 2018;55(3):353–68. <https://doi.org/10.1139/cgj-2016-0633>.
- Aikawa A. Dynamic characterisation of a ballast layer subject to traffic impact loads using three-dimensional sensing stones and a special sensing sleeper. *Constr Build Mater* 2015;92:23–30. <https://doi.org/10.1016/j.conbuildmat.2014.06.005>.
- Sas W, Gluchowski A, Bursa B, Szymański A. Energy-based analysis of permanent strain behaviour of cohesive soil under cyclic loading. *Acta Geophys* 2017;65(2): 331–44. <https://doi.org/10.1007/s11600-017-0028-7>.
- R.T. Qu, Z.J. Zhang, P. Zhang, Z.Q. Liu, Z.F. Zhang. Generalized energy failure criterion. *Scientific Reports* 6 (1). doi:10.1038/srep23359. URL: doi: 10.1038/srep23359.
- Birgisson B, Wang J, Roque R, Sangpetngam B. Numerical implementation of a strain energy-based fracture model for HMA materials. *Road Mater Pavement Des* 2007;8(1):7–45. <https://doi.org/10.1080/14680629.2007.9690065>.
- Sadri M, Lu T, Steenbergen M. Railway track degradation: The contribution of a spatially variant support stiffness - local variation. *J Sound Vib* 2019;455:203–20. <https://doi.org/10.1016/j.jsv.2019.05.006>.
- Paixão A, Varandas JN, Fortunato E, Calçada R. Numerical simulations to improve the use of under sleeper pads at transition zones to railway bridges. *Eng Struct* 2018;164:169–82. <https://doi.org/10.1016/j.engstruct.2018.03.005>.
- P. Punetha, K. Maharjan, S. Nimbalkar, Finite element modeling of the dynamic response of critical zones in a ballasted railway track, *Frontiers in Built Environment* 7. doi:10.3389/fbuil.2021.660292.
- G. Ognibene, W. Powrie, L. Le Pen, J. Harkness, Analysis of a bridge approach: Long-term behaviour from short-term response, 2019.
- Wang H, Markine V, Liu X. Experimental analysis of railway track settlement in transition zones. *Proc Inst Mech Eng, Part F: J Rail Rapid Transit* 2017;232(6): 1774–89. <https://doi.org/10.1177/0954409717748789>.
- ABAQUS/Standard User's Manual, Version 6.9, Dassault Systèmes Simulia Corp, United States.
- Jain A, van Dalen KN, Metrikine AV, B. Faragou A, Steenbergen MJMM. Comparative analysis of the dynamic amplifications due to inhomogeneities at railway transition zones. In: *Railways 2022, Proceedings of the Fifth International Conference on Railway Technology: Research, Development and Maintenance, Civil-Comp Press, ISSN: 2753-3239*. <http://dx.doi.org/10.4203/ccc.1.19.1>.
- Wang H, Markine V. Modelling of the long-term behaviour of transition zones: Prediction of track settlement. *Eng Struct* 2018;156:294–304. <https://doi.org/10.1016/j.engstruct.2017.11.038>.
- Wang H. Measurement, assessment, analysis and improvement of transition zones in railway track. Ph.D. thesis 2019. <https://doi.org/10.4233/UUID:73830B2C-DEB1-4DA9-B19C-5E848C5CFA4D>.
- ABAQUS Online Documentation: Version 6.6-1, Dassault Systèmes Simulia Corp, United States.
- Indraratna B, Thakur PK, Vinod JS. Experimental and numerical study of railway ballast behavior under cyclic loading. *Int J Geomech* 2010;10(4):136–44. [https://doi.org/10.1061/\(asce\)gm.1943-5622.0000055](https://doi.org/10.1061/(asce)gm.1943-5622.0000055).
- Wang H, Chang L, Markine V. Structural health monitoring of railway transition zones using satellite radar data. *Sensors* 2018;18(2):413. <https://doi.org/10.3390/s18020413>.
- Wang H, Markine VL. Methodology for the comprehensive analysis of railway transition zones. *Comput Geotech* 2018;99:64–79. <https://doi.org/10.1016/j.compegeo.2018.03.001>.
- Shahraki M, Warnakulasooriya C, Witt KJ. Numerical study of transition zone between ballasted and ballastless railway track. *Transport Geotech* 2015;3:58–67. <https://doi.org/10.1016/j.trgeo.2015.05.001>.
- Stark TD, Wilk ST. Root cause of differential movement at bridge transition zones. *Proc Inst Mech Eng, Part F: J Rail Rapid Transit* 2015;230(4):1257–69. <https://doi.org/10.1177/0954409715589620>.

- [40] Jain A, Acito M, Chesi C. Seismic sequence of 2016–17: Linear and non-linear interpretation models for evolution of damage in san francesco church, amatrice. *Eng Struct* 2020;211:110418. <https://doi.org/10.1016/j.engstruct.2020.110418>.
- [41] Jain A, Acito M, Chesi C, Magrinelli E. The seismic sequence of 2016–2017 in central Italy: a numerical insight on the survival of the civic tower in amatrice. *Bull Earthq Eng* 2019;18(4):1371–400. <https://doi.org/10.1007/s10518-019-00750-w>.
- [42] Acito M, Magrinelli E, Milani G, Tiberti S. Seismic vulnerability of masonry buildings: Numerical insight on damage causes for residential buildings by the 2016 central italy seismic sequence and evaluation of strengthening techniques. *J Build Eng* 2020;28:101081. <https://doi.org/10.1016/j.job.2019.101081>.
- [43] Jain A, Metrikine A, Steenbergen M, van Dalen K. Railway transition zones: evaluation of existing transition structures and a newly proposed transition structure. *Int J Rail Transport* 2023:1–21. <https://doi.org/10.1080/23248378.2023.2272668>.
- [44] Jain A, Marykovskiy Y, Metrikine A, van Dalen K. Quantifying the impact of stiffness distributions on the dynamic behaviour of railway transition zones. *Transport Geotech* 2024;45:101211. <https://doi.org/10.1016/j.trgeo.2024.101211>. ISSN: 2214-3912.