

Fracture simulation of welded RHS X-joints using GTN damage model

Yan, Rui; Xin, Haohui; Mela, Kristo; El Bamby, Hagar; Veljkovic, Milan

DOI

[10.1177/13694332221137175](https://doi.org/10.1177/13694332221137175)

Publication date

2022

Document Version

Final published version

Published in

Advances in Structural Engineering

Citation (APA)

Yan, R., Xin, H., Mela, K., El Bamby, H., & Veljkovic, M. (2022). Fracture simulation of welded RHS X-joints using GTN damage model. *Advances in Structural Engineering*, 26(12), 2140-2159.
<https://doi.org/10.1177/13694332221137175>

Important note

To cite this publication, please use the final published version (if applicable).
Please check the document version above.

Copyright

Other than for strictly personal use, it is not permitted to download, forward or distribute the text or part of it, without the consent of the author(s) and/or copyright holder(s), unless the work is under an open content license such as Creative Commons.

Takedown policy

Please contact us and provide details if you believe this document breaches copyrights.
We will remove access to the work immediately and investigate your claim.

Fracture simulation of welded RHS X-joints using GTN damage model

Rui Yan¹ , Haohui Xin², Kristo Mela³, Hagar El Bamby¹ and Milan Veljkovic¹

Advances in Structural Engineering
2022, Vol. 0(0) 1–20
© The Author(s) 2022



Article reuse guidelines:

sagepub.com/journals-permissions
DOI: 10.1177/13694332221137175
journals.sagepub.com/home/ase



Abstract

A welded rectangular hollow section (RHS) X-joint exposed to tension loading has three typical fracture-related failure modes: Punching shear failure (PSF), Brace failure (BF), and Chord side wall failure (CSWF). Prediction of these failure modes by finite element (FE) simulations requires modelling of the material damage. An appropriate damage model accurately predicts the behaviour of the fracture zone and provides the necessary information to improve design rules for welded high-strength steel (HSS) RHS X-joints based on parametric studies using validated model. In this paper, the parameters of the Gurson-Tvergaard-Needleman (GTN) damage model are calibrated for the base material (BM) and the heat-affected zone (HAZ) of butt-welded cold-formed RHS connections, no fracture appeared in the weld. A computational homogenisation analysis is carried out using representative volume element (RVE) models to calibrate the pressure-dependent yield surface parameters of the GTN damage model, considering the different combinations of the accumulated initial hardening strain and the void volume fraction (VVF) due to a varying stress triaxiality. The critical and final VVFs are calibrated against tensile coupon tests. Finally, the GTN damage models calibrated for BM and HAZ are used in the fracture simulation of nine welded cold-formed RHS X-joints in monotonic tension. The FE model successfully predicts the experimental load-displacement relationships and fractured zone, indicating the calibrated GTN models could effectively be used in parametric study of welded cold-formed RHS X-joints. Finally, possible improvements to the used FE model are outlined for future studies.

Keywords

Gurson-Tvergaard-Needleman damage model, heat-affected zone, high-strength steel, welded hollow section joints

Introduction

High-strength steel (HSS) has become more readily available in recent years, owing to advanced material manufacturing techniques, e.g. Thermo-mechanical control process (TMCP) and Quenching & Tempering (QT). Additional rules are supplemented in EN 1993-1-12 (2007) to extend the existing design rules for mild steels ($f_y \leq 460$ MPa) to HSS ($460 \text{ MPa} < f_y \leq 700$ MPa). A material factor ($C_f = 0.8$ for $460 \text{ MPa} < f_y \leq 700$ MPa steels) is stipulated to reduce the HSS material yield strength in designing welded hollow section joints, accounting for possible joint resistance degradations due to the lower ductility of HSS compared to mild steels. C_f is increased from 0.8 to 0.86 for $460 \text{ MPa} < f_y \leq 550$ MPa steels in the updated revision prEN1993-1-8 (2021), which also prescribes that the material design yield strength is limited to 0.8 times the ultimate strength (f_u) for the punching shear failure (PSF) and the tension brace failure (BF). However,

implementing both C_f and the $0.8f_u$ restriction, may result in a conservative joint design resistance, reducing the benefits of using HSS (Yan et al., 2022a). That was one of the motivations for undertaking an extensive experimental program on welded X-joints in tension and numerical studies to investigate the validity of C_f and the $0.8f_u$ restriction presented in this paper. Yan et al. (2022a) found

¹Department of Engineering Structures, Delft University of Technology, Delft, The Netherlands

²School of Human Settlements and Civil Engineering, Xi'an Jiaotong University, Xi'an, China

³Faculty of Built Environment, Tampere University, Tampere, Finland

Corresponding author:

Rui Yan, Department of Engineering Structures, Faculty of Civil Engineering & Geosciences, Delft University of Technology, Stevinweg 1, Delft 2628CN, The Netherlands.

Email: r.yan@tudelft.nl

that neither C_f nor the $0.8f_u$ restriction is necessary for designing HSS rectangular hollow section (RHS) X-joints in tension based on the experimental data presented in (Becque and Wilkinson, 2017; Björk and Saastamoinen, 2012; Feldmann et al., 2016; Tuominen and Björk, 2017; Yan et al., 2022a). The mechanical behaviour of joints beyond the experimental configuration is commonly studied using a verified finite element (FE) model (Björk and Saastamoinen, 2012; Huang et al., 2021; Kim et al., 2019; Lan et al., 2019, 2021; Lee and Kim, 2018; Lee et al., 2017; Liu et al., 2018; Ma et al., 2015; Mohan and Wilkinson, 2022; Tuominen and Björk, 2017; Xin et al., 2021). As the joints fail by a fracture in the heat-affected zone (HAZ) or in the base material (BM), it is essential to conduct an advanced numerical study considering both the stress-strain relationship of HAZ and the material damage model. Such advanced numerical models enable a better understanding of the various failure mechanisms and provide confidence in numerically generated data in the parametric study for improvements of the design rules of welded hollow section joints.

Different damage models have been implemented in the fracture simulation of welded joints in recent years (Huang et al., 2021; Liu et al., 2018; Ma et al., 2015; Mohan and Wilkinson, 2022; Xin and Veljkovic, 2021). Ma et al. (2015) extended a damage-mechanics-based model to predict PSF in hollow section joints, considering the effect of the stress triaxiality and the Lode angle. It was argued that the fracture strain at the fracture initiation point of the joint would be overestimated under a shear-dominated stress state if the effect of the Lode angle was not considered in the damage model. However, the paper did not present the global load-deformation relationship from the model without considering the Lode angle. The effect of the high fracture strain in limited number of elements on the joint global behaviour is vague. Liu et al. (2018) proposed a shear-modified Gurson-Tvergaard-Needleman (GTN) model (Tvergaard and Needleman, 1984) to simulate the fracture propagation of the X-joint PSF. The shear-modified GTN model was first calibrated against traditional tensile specimens, notched specimens, and shear specimens for the BM of the hollow sections and the weld metal (WM). The calibrated shear-modified GTN model was subsequently implemented in the X-joint fracture simulation. It was found that the original GTN model, without considering the material shear damage, could properly predict the crack initiation point (the ultimate resistance), but failed to predict the fracture propagation under a shear-dominated stress state. The shear-modified GTN model showed a better performance in predicting the fracture process after the peak load, compared to the original GTN model. The accurate prediction of the ultimate state considering the Lode angle is necessary at a low triaxiality in the fracture zone, but the Lode angle has

limited influence on the fracture plastic strain at a high stress triaxiality and can be neglected (Bai and Wierzbicki, 2008; Cao et al., 2014; Huang et al., 2020; Ma et al., 2015).

Although many numerical studies have been carried out on welded hollow section joints, the mechanical and geometric properties of the HAZ are rarely considered in the FE analysis, which may lead to an unsafe prediction of the joint resistance, especially for HSS joints. Lan et al. (2019) conducted experimental and numerical studies on the welded HSS RHS X-joints in compression. Heat-affected zone was modelled based on some simplified mechanical and geometric assumptions. It was concluded that the strength degradation of the HAZ significantly influenced the joint resistance.

The mechanical properties of HAZ have been reported by many researchers (Amraei et al., 2019; Amraei et al., 2020; Cai et al., 2022; Chen et al., 2019; Peng et al., 2019; Peng et al., 2018; Yan et al., 2021a; Yan et al., 2022b; Yan et al., 2022c). Yan et al. (2022b) found a 13% yield and 4% ultimate strength degradation in HAZ compared to BM in S355 and S500 butt-welded TMCP cold-formed RHS connections, while a larger strength reduction, 24% and 19% for the yield strength and the ultimate strength respectively, were observed in S700 connections. A constitutive model correlating to BM mechanical properties was proposed for HAZ, which was established based on experimental and numerical studies on the tensile behaviour of milled welded coupon specimens with a butt weld in the middle. The HAZ strength degradation in butt-welded connections was also examined in (Cai et al., 2022) using the Vickers hardness test. The strength of HAZ was predicted according to the empirical relationship between hardness results and material strength. The HAZ strength degradation varies in a very similar range with less than a 5% difference compared to the results presented in (Yan et al., 2022b) concerning the material strength ratio and the complete welded connection strength ratio. Moreover, Cai et al. (2022) investigated the effect of the BM processing method (TMCP or QT) on the HAZ mechanical properties, which is not considered in the current design rules and might lead to an unsafe design for HSS or ultra HSS welded hollow section joints. It is worth mentioning that the HAZ strength degradation is closely related to the welding technique and parameters used. The HAZ strength could be comparable to the BM if appropriate welding technique and parameters are employed, as demonstrated in (Amraei et al., 2019).

In this paper, the fracture simulation of nine welded cold-formed RHS X-joints is conducted using the GTN damage model. First, computational homogenization analysis is carried out to identify the dependency of the yield surface on the stress triaxiality for BM and HAZ, following the method proposed for BM in (Yan et al., 2021b). Two fracture-related parameters (critical void




Figure 1. Schematic of a butt-welded X-joint.

Table 1. Measured dimensions of X-joint. (See Figure 1 for the definition of dimensions).

Code-name	Steel grade	b_0 (mm)	h_0 (mm)	t_0 (mm)	b_1 (mm)	h_1 (mm)	t_1 (mm)	β	a_{sideA} (mm)	a_{sideB} (mm)
XS355A1	S355	199.0	100.4	7.9	50.2	100.3	5.0	0.25	5.1	5.3
XS355A2		159.6	160.5	10.0	140.1	139.6	8.3	0.88	-	6.2
XS355A3		150.5	149.9	6.1	149.9	150.4	6.0	1	-	5.4
XS500A1	S500	200.0	101.1	7.9	90.5	159.9	7.9	0.45	6.6	6.6
XS500A2		160.9	160.8	9.8	140.4	140.4	7.9	0.87	-	8.6
XS500A3		150.7	150.2	6.0	150.5	150.3	6.0	1	-	5.1
XS700A1	S700	120.4	120.3	7.9	51.0	153.2	6.0	0.42	6.3	6.2
XS700A2		161.5	160.5	9.9	80.5	100.7	4.1	0.5	5.5	5.6
XS700A3		139.9	140.4	5.9	120.6	80.4	6.0	0.86	-	5.4

volume fraction (VVF) f_c and final VVF f_f) are determined by simulating the tensile coupon tests, including standard coupon specimens (Metallic materials - Tensile testing - Part 1: Method of test at room temperature, 2019) and milled, to the 3 mm thick mid part (Yan et al., 2021a, 2022c), welded coupon specimens. Finally, the calibrated GTN damage model is implemented in the fracture simulation of welded RHS X-joints in tension. A good agreement is obtained between the experimental and FE results, indicating that the calibrated GTN model for HAZ and BM can effectively predict fracture failure in welded RHS X-joints considered in the experiments.

Experiments

Tensile X-joint tests

An X-joint consists of two braces and one chord, as shown in Figure 1. The braces are symmetrically welded on two opposite surfaces of the chord. In the test series of this paper, the brace was welded to the chord with a full-penetration butt weld. An example of the butt weld is presented in Figure 1. The weld is composed of five welding passes which are the root (pass 1), the fill (passes 2 and 3), and the cap (passes 4 and 5), where the cap passes result in an extra fillet weld. Note that the number of the fill




Figure 2. Measurements of X-joint tests.

and the cap welding passes may vary depending on the brace thickness.

9 X-joints made of cold-formed RHS were tested with tension load applied to the braces. Three specimens with different brace width to chord width ratios ($\beta = b_1/b_0$) were fabricated for each steel grade (S355, S500, and S700). The measured dimensions of each specimen are presented in Table 1. The chord and the brace length were 1.5 m and 0.4 m, respectively. The outer radius for nominal 4 mm, 5 mm, 6 mm, 8 mm, and 10 mm tubes were 8.5 mm, 9 mm, 13 mm, 20 mm, and 25 mm, respectively. The throat thickness (a) of the extra fillet weld was measured, except for Side A (see Figure 1) of joints if $\beta > 0.85$. The longitudinal seam weld in the brace is often positioned on Side B, as the seam close to the chord corner might have a negative effect on the joint behaviour. However, the seam can be on the wider side of RHS, which corresponds to face Side A, as it appeared in XS700A1 specimen. Hence, the seam side of the brace is not distinguished in the presented study, because no premature failure was observed initiating from the brace seam.

A workshop proficient in welding HSSs was employed to carry out to fabricate the specimens using their own welding procedures. The main reason for employing an industrial workshop rather than performing the welding in laboratory conditions was to emulate a welding conditions used in practice. The filler metal Carbofil 1 was used for S355 joints, whereas S500 and S700 joints were welded by Union NiMoCr. The workshop reported the minimum

preheat temperature, the maximum interpass temperature, and the heat input of the metal active gas (MAG) welding process were 20°C, 200°C, and 1–1.4 kJ/mm, respectively. Other welding parameters were not provided.

The tensile tests were conducted in two testing setups. Specimens XS355A1, XS500A1, XS500A2, XS500A3, and XS700A1 were tested in a 2 MN setup, while the rest of the specimens were tested in a 10 MN setup. The longitudinal deformation of the specimen was measured using 4 Linear Variable Differential Transformers (LVDTs) based on a $2b_0$ initial gauge length, as shown in Figure 2. For more details of the experiments and results, see (Yan et al., 2022a).

Tensile coupon tests

Standard coupon specimens were fabricated from the wall opposite the longitudinal weld of RHS in X-joints, as shown in Figure 3(a), to obtain the stress-strain relationship of BM. The initial gauge length of the coupon test was 50 mm based on a 5.65 proportional coefficient (Metallic materials - Tensile testing - Part 1: Method of test at room temperature, 2019).

In addition, nine cold-formed RHS profiles, from the same batch as the profiles used for the X-joints, were employed to obtain the stress-strain relationship of HAZ concerning three steel grades (S355, S500, and S700) and three thicknesses for each steel grade (4 or 5 mm, 8 mm, and 10 mm). Two short pieces, 200 mm long, of the hollow section were welded by a single-V full penetration butt weld, as shown in Figure 4. The name of the welded short tube consists of the steel grade and the thickness. For example, S700t8 represents the profile with S700 steel grade and a 8 mm thickness. The same welding parameters and filler metals used for the X-joints were adopted for welding the short profiles.

Two types of specimens were cut out from the flat wall of the tube opposite the side with the longitudinal weld, as shown in Figure 3(b). The standard coupon specimen and the welded coupon specimen were used to obtain the BM and HAZ stress-strain relationships, respectively. The welded coupon specimen was milled to a central thickness zone of 3 mm to have the width of HAZ through the thickness as constant as possible. It is worth mentioning that the milled welded coupon specimen failed in HAZ, such that the complete stress-strain relationship of HAZ, including the softening part, was obtained. Figure 5 presents the coupon test setup. Two monitoring methods were used: an extensometer and a 3D DIC (ARAMIS) to measure the elongation and complete deformation of the specimen, respectively, from two opposite sides of the specimen. An initial bow existed in the standard coupon specimen due to residual stress generated in the tube during the cold-forming process. The deformations measured from two opposite sides were averaged.




Figure 3. Coupon specimens for BM and HAZ. (a) Standard coupon specimen cutting scheme, (b) Welded coupon specimen cutting scheme.




Figure 4. Welded tubes. (a) S355t5. (b) S355t8. (c) S355t10. (d) S500t4. (e) S500t8. (f) S500t10. (g) S700t5. (h) S700t8. (i) S700t10.




Figure 5. Measurements of Coupon tests.

For the milled welded coupon specimen, the testing result of DIC was used, as the specimen was not curved.

Numerical models

Gurson-Tvergaard-Needleman damage model

The GTN damage model (Tvergaard and Needleman, 1984) is employed to simulate the fracture at monotonic loading in this paper. Equation (1) presents the yield surface of the GTN model. The shape of the yield surface is defined by three parameters q_1 , q_2 , and q_3 , which are calibrated in a homogenization procedure, see Sections

'Representative volume element models', 'Correlation between VVF and initial hardening strain', and 'Yield surface parameters (q_1 and q_2)' below. σ_m and σ_{eq} are the hydrostatic pressure, see equation (2) and the von Mises equivalent stress, see equation (3), respectively. σ_y is the flow stress of the undamaged material matrix.

$$\phi = \left(\frac{\sigma_{eq}}{\sigma_y}\right)^2 + 2q_1 f^* \cosh\left(\frac{3q_2 \sigma_m}{2\sigma_y}\right) - 1 - q_3 f^{*2} = 0 \quad (1)$$

$$\sigma_m = \frac{1}{3} \sigma_{ij} \delta_{ij} \quad (2)$$

$$\sigma_{eq} = \sqrt{\frac{3}{2} \left(\sigma_{ij} - \frac{1}{3} \sigma_{ij} \delta_{ij}\right) \left(\sigma_{ij} - \frac{1}{3} \sigma_{ij} \delta_{ij}\right)} \quad (3)$$

where σ_{ij} and δ_{ij} are the stress tensor and the Kronecker delta, respectively. Due to the decohesion of the particle-matrix interface and microcracking, new voids may appear during the loading process, resulting in a void-nucleation-related increment in the VVF (\dot{f}_n). The nucleation increment follows a normal distribution with respect to the increment of the equivalent plastic strain ($\dot{\epsilon}_{eq}^{pl}$), as shown in equation (4). The parameters f_n , ϵ_n , and S_n are the total nucleated VVF, the mean value of the normal distribution of the nucleation strain, and the standard deviation (SD), respectively.

$$\dot{f}_n = A \dot{\epsilon}_{eq}^{pl} \quad (4)$$

$$A = \frac{f_n}{S_n \sqrt{2\pi}} e^{-\left[\frac{1}{2} \left(\frac{\epsilon_{eq}^{pl} - \epsilon_n}{S_n}\right)^2\right]}$$

The existing void would grow accompanying the plastic deformation according to the volume preservation assumption. The increment of the void growth (\dot{f}_g) depends on the plastic hydrostatic strain rate ($\dot{\epsilon}_{kk}^{pl}$) and VVF (f), as shown in equation (5). Considering the above-mentioned two VVF increments, the increment of the total VVF (\dot{f}) is determined (see equation (6)).

$$\dot{f}_g = (1 - f) \dot{\epsilon}_{kk}^{pl} \quad (5)$$

$$\dot{f} = \dot{f}_n + \dot{f}_g \quad (6)$$

The expression of the modified VVF (f^*) is given in equation (7). A linear interpolation is used to enlarge VVF based on a critical VVF (f_c) and a final VVF (f_f). The amplification of VVF starts and completes when f_c and f_f is reached, respectively. When the damage variable VVF reaches f_f , the material fails. The parameters f_c and f_f describe the process of the void coalescence. f_c is VVF at the initiation

of the void coalescence. f_f corresponds to the end of the void coalescence but does not have a physical meaning, as f^* is modified to f_u^* , which is VVF at the onset of failure.

$$f^* = \begin{cases} f & f < f_c \\ f_c + K(f - f_c) & f_c \leq f < f_f \\ f_u^* & f \geq f_f \end{cases} \quad K = \frac{f_u^* - f_c}{f_f - f_c} \quad (7)$$

Undamaged true stress-true strain relationship

The undamaged true stress-true strain relationship consists of pre- and post-necking parts. The pre-necking part is obtained from the tensile coupon test by converting the engineering stress-strain relationship until the ultimate strength to the true stress-strain relationship following equation (8).

$$\begin{aligned} \sigma_t &= \sigma_e (1 + \epsilon_e) \\ \epsilon_t &= \ln(1 + \epsilon_e) \end{aligned} \quad (8)$$

where subscripts 'e' and 't' denote 'engineering' and 'true', respectively. The post-necking part is generated based on the extrapolation of three theoretical models, which are the Voce model (Voce, 1948) (equation (9)), the Swift model (Swift, 1952) (equation (10)), and the linear model (Ling, 2004) (equation (11)). The parameters of the theoretical models are determined by fitting the pre-necking data using the least-squares method.

$$\sigma_{t,V} = k_0 + Q(1 - e^{-\beta_0 \epsilon_t}) \quad (9)$$

$$\sigma_{t,S} = k(\epsilon_t + \epsilon_0)^n \quad (10)$$

$$\sigma_{t,L} = a + b\epsilon_t \quad (11)$$

where k_0 , Q , β_0 are the Voce parameters; k , ϵ_0 , n are the Swift parameters; and a , b are the linear parameters. A linear combination of the Swift model and the linear model using a weighting factor W is adopted to generate the undamaged true stress-true strain relationship of BM, as shown in equation (12). The Swift model and the Voce model are used for WM and HAZ, respectively. A detailed illustration for choosing the specific material model is presented in Section 'Fracture parameters (f_c and f_f)'.

$$\sigma_t = W\sigma_{t,L} + (1 - W)\sigma_{t,S} \quad (12)$$

Representative volume element models

The steel material contains voids and steel matrix. It is impossible to create the voids in the coupon specimens or in the welded joints, as the extremely small voids results in meshing and computation efficiency problems. Hence, the voids are created in a unit cell representing a homogenised material, as shown in Figure 6. The mechanical response of




Figure 6. An example of the representative volume element model.

Table 2. Void details of RVEs.

f (%)	0.1	0.3	0.6	1.0	1.6	2.3	3.1	4.0	5.0
N	20	20	20	40	40	40	40	40	40
R (mm)	0.0229	0.0330	0.0415	0.0391	0.0457	0.0516	0.0570	0.0620	0.0668
f (%)	6.0	7.0	8.1	9.1	10.0	11.0	15.0	20.0	25.0
N	40	40	80	80	80	80	80	80	80
R (mm)	0.0710	0.0748	0.0623	0.0648	0.0668	0.0690	0.0765	0.0842	0.0907

Table 3. Parameters for different loading conditions.

Loading conditions	1	2	3	4	5	6
α_1	1	1	1	1	1	1
α_2	0.1	0.3	0.5	0.7	0.9	1.2

the homogenised material is obtained by varying boundary conditions. Accordingly, some constitutive parameters, such as q_1 and q_2 in this paper, could be determined based on the simulation results. This simulation procedure is called the computational homogenisation analysis.

The ABAQUS:2021 software package (ABAQUS, 2021) is used to conduct the FE analysis. The computational homogenisation analysis is performed based on 18 representative volume element (RVE) models with VVF varying from 0.1% to 25%. The side length of the cubic model is 1 mm. Non-overlapping voids with a constant radius R are randomly scattered in the unit cell, as presented in Figure 6. All RVE models mesh with a 0.1 mm universal mesh, which is sufficient to avoid convergence problems as illustrated in (Fritzen et al., 2012; Yan et al., 2020, 2021b). Table 2 presents the detailed information of each RVE regarding VVF, the number of voids (N), and the radius of the void (R). The rationale for the selected VVF values is given in Section ‘Correlation between VVF and initial hardening strain’. Correlation between VVF and initial hardening strain.

A periodic boundary condition adopted by (Fritzen et al., 2012; Yan et al., 2020, 2021b) is applied to the RVE model on three pairs of opposite surfaces. A uniform displacement along the normal of a surface is applied on different surfaces of the RVE model to vary the stress triaxiality in the model. Fritzen et al. (2012) proposed two parameters, α_1 and α_2 , to control the strain-driven load, as shown in equation (13). As the maximum stress triaxiality among all X-joint models is below 3, the relationship between the hydrostatic pressure dependency and the macroscopic yield surface is investigated by applying six loading conditions. The parameters for different loading conditions are presented in Table 3.

$$\begin{bmatrix} \dot{\epsilon} \\ \dot{\epsilon} \\ \dot{\epsilon} \end{bmatrix} = \alpha_1 \begin{bmatrix} 1 & 0 & 0 \\ 0 & -1 & 0 \\ 0 & 0 & 0 \end{bmatrix} + \alpha_2 \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{bmatrix} \quad (13)$$

Coupon specimen models

FE models are created based on the measured dimensions for the standard coupon specimen and the milled welded coupon specimen to calibrate the GTN parameters for BM and HAZ, as shown in Figure 7. The welded coupon specimen contains two HAZ zones and one WM zone. The width was determined using the method proposed by Yan et al., 2021a, 2022c. The FE models finely mesh with 0.5 mm element size in the central part




Figure 7. Finite element model of coupon specimens. (a) Standard coupon specimen. (b) Milled welded coupon specimen.




Figure 8. Finite element model for X-joints.

50 mm long, the base length where the extensometer was installed. The remaining part uses a coarse mesh in the loading direction. In order to reduce the computational burden, the grip part of the specimen is not created. Two reference points, RP1 and RP2, are employed to control all three translations and three rotations of the end surfaces using the multi-point beam constraint (MPC beam). A positive displacement in the Y direction is applied at RP2, while the other degrees of freedom of RP1 and RP2 are fixed. The explicit solver with a 100 s period and a 0.0001 s target time increment is used to perform the quasi-static analysis. Eight-node hexahedral solid elements with reduced integration (C3D8R) are employed in the model.

X-joint models

FE models are generated to verify the GTN damage model and the experiments. The models are built up with the




Figure 9. HAZ and WM regions in a weld zone.

measured geometric dimension, as shown in Table 1. Only a quarter of the joint is created to reduce the computational burden. Figure 8 shows an example of the FE model for the specimen XS500A2. Reference points (RP1 and RP2) are made at the centre of the entire RHS end surfaces (marked with yellow). Each reference point controls all translations and rotations of the corresponding end surface through the MPC beam constraint. The loading is applied as a positive displacement at RP1 in the Y direction. The remaining degrees of freedom at reference points are fixed. In addition, symmetry boundary conditions are applied on Surface 1 and Surface 2, see Figure 8. The quasi-static analysis is conducted using the explicit solver with a 100 s period and a 0.0001 s target time increment.

The weld zone consists of five material regions: Chord, Chord HAZ, WM, Brace, and Brace HAZ. Figure 9 shows the HAZ and WM regions in the FE model. The HAZ width in the butt welded tubes, referring to Figure 3(b), is measured based on the Vickers hardness tests (Yan et al., 2022b). It was found that the majority (92%) of the HAZ width varies between 2 mm and 4 mm, with an average 3.2 mm width regardless of the steel grade and the thickness of the profile. Hence, a 3.2 mm HAZ width is used in all X-joint models. The HAZ region in the brace is oriented parallel to the bevelled surface, while the HAZ in the chord is oriented through the thickness of the cross-section.




Figure 10. Examples of mesh used in the FE models. (a) XS700A1 with the C3D8R element. (b) XS500A2 with the C3D10 element.




Figure 11. True stress-strain relationship with different initial hardening strains.

The C3D8R element is used for modelling joints with $\beta < 0.8$, i.e. the joints XS355A1, XS500A1, XS700A1, and XS700A2 (see Table 1). A 0.5 mm mesh size is adopted for critical regions concerning HAZ, WM, and part of BM close to HAZ. The BM mesh size along the profile length direction gradually changes to 5 mm. Due to the complex geometry at the chord corner of joints with $\beta > 0.8$ (XS355A2, XS355A3, XS500A2, XS500A3, and XS700A3), it is not possible to mesh using the C3D8R element. The ten-node tetrahedral element C3D10 is employed. A universal 1 mm mesh size is used for HAZ, WM and part of BM close to HAZ. Note that the chord front face of XS355A3 also meshed with 1 mm elements as a chord side wall failure (CSWF) appeared in the experiment. Two examples of FE mesh using C3D8R and C3D10 elements are presented in Figure 10(a) and (b), respectively.

Calibration of GTN parameters

Correlation between VVF and initial hardening strain

The input data (stress-strain relationship) in the RVE model is considered the constitutive model of the steel matrix, excluding the effect of the void on the stress-strain relationship of the material. The RVE model contains the steel matrix and the void, representing a material unit in the real

specimen. It can be used to simulate the behaviour of the material unit under different loading conditions and various stages of damage. Hence, the mechanical response of the material unit under different stress states could be obtained from the RVE model. It is assumed that the volume of the steel matrix is unchangeable, indicating that the volume of the homogenised material may change during loading, as the void volume changes. Hence, the plastic hydrostatic strain rate, see equation (5), is not zero.

With different stress triaxialities, the evolution of the plastic strain component is different. Take two sets of the plastic strain increment with the same plastic hydrostatic strain rate (0.003) for instance. The first set of the plastic strain rate is 0.011, 0.001, and -0.009 for $\dot{\epsilon}_1$, $\dot{\epsilon}_2$, and $\dot{\epsilon}_3$, respectively. The second set of the plastic strain rate is 0.012, 0.001, and -0.010 for $\dot{\epsilon}_1$, $\dot{\epsilon}_2$, and $\dot{\epsilon}_3$, respectively. The VVF increment of these two examples is identical since the plastic hydrostatic strain rate is the same. However, the equivalent plastic strain rate of the first and second set is 0.012 and 0.013, respectively. It indicates that a given VVF corresponds to a range of equivalent plastic strain instead of a unique value, and vice versa. Hence, for analysing the RVE model with VVF larger than the initial VVF, a modified stress-strain relationship should be used. The effect of the various combinations of initial hardening strains and VVFs on the material yield surface is evaluated.

Table 4. The accumulated initial hardening strains for different VVFs.

f (%)	0.1	0.3	0.6	1.0	1.6	2.3	3.1	4.0	5.0
$\Delta\epsilon_i$	—	0.005	0.01	0.02	0.03	0.04	0.05	0.06	0.07
$\Delta\epsilon_m$	0	0.03	0.05	0.08	0.1	0.16	0.19	0.22	0.25
$\Delta\epsilon_h$	—	0.05	0.1	0.16	0.22	0.27	0.32	0.37	0.42
f (%)	6.0	7.0	8.1	9.1	10.0	11.0	15.0	20.0	25.0
$\Delta\epsilon_i$	0.08	0.09	0.1	0.11	0.12	0.13	0.17	0.22	0.27
$\Delta\epsilon_m$	0.27	0.3	0.32	0.36	0.38	0.4	0.51	0.63	0.76
$\Delta\epsilon_h$	0.47	0.52	0.56	0.6	0.64	0.68	0.84	1.04	1.24




Figure 12. Example of RVE results ($f = 5\%$, 0.07 strain hardening, Swift model extrapolation). (a) σ_{eq} - ϵ_{eq} relationships. (b) σ_{eq} - σ_m relationships.

Table 5. Calibrated parameter q_1 .

f (%)	0.1	0.3	0.6	1.0	1.6	2.3	3.1	4.0	5.0
$q_{1,\Delta\epsilon_i}$	—	2.20	2.38	2.22	2.30	2.12	2.08	2.04	1.99
$q_{1,\Delta\epsilon_m}$	2.91	2.56	2.54	2.32	2.31	2.12	2.10	2.05	2.00
$q_{1,\Delta\epsilon_h}$	—	2.61	2.57	2.32	2.32	2.12	2.10	2.06	2.00
f (%)	6.0	7.0	8.1	9.1	10.0	11.0	15.0	20.0	25.0
$q_{1,\Delta\epsilon_i}$	1.85	1.99	1.76	1.79	1.77	1.66	1.62	1.57	1.51
$q_{1,\Delta\epsilon_m}$	1.86	2.00	1.77	1.79	1.78	1.66	1.61	1.57	1.51
$q_{1,\Delta\epsilon_h}$	1.86	2.00	1.77	1.79	1.78	1.67	1.59	1.57	1.51




Figure 13. Materials with a similar strain hardening behaviour. (a) BM. (b) HAZ.

Table 6. Material categories.

	Analysed material	Similar material
BM	XS700A3B	—
	XS700A2B	XS700A1B
	XS500A2B	XS500A1B, XS355A2B, XS355A1B, S355t5B, S355t8B, S500t8B
	XS355A3B	XS500A3B
HAZ	S700t10H	S500t4H, S500t10H, S700t8H
	S355t8H	S355t5H, S355t10H, S500t8H, S700t5H

Table 7. Determined constitutive parameters.

Parameters	BM								HAZ	
	XS700A3B		XS700A2B		XS500A2B		XS355A3B		S700t10H	S355t8H
	L	S	L	S	L	S	L	S	V	V
A	1.263	1.338	1.294	1.351	1.288	1.334	1.363	1.383	1.417	1.443
B	-0.132	-0.106	-0.127	-0.116	-0.125	-0.107	-0.094	-0.085	-0.079	-0.068
q_2	0.968	1.016	0.961	1.006	0.982	1.014	1.010	1.019	1.015	1.015




Figure 14. Determination of constitutive parameters. (a) Weighting factor. (b) VVF contour plot at the failure point. (c) f_c and f_i . (d) Final fracture.

Figure 11 depicts a schematic drawing of modifying the true stress-strain relationship based on different initial hardening strains. The black line represents the original true stress-strain relationship. The red, blue, and yellow lines are the modified relationships with an ascending level

of the initial hardening strain $\Delta\epsilon_{t1}$, $\Delta\epsilon_{t2}$, and $\Delta\epsilon_{t3}$, respectively. The initial hardening strain of the modified relationship is set to zero (graphically offset the curves) to generate input data for the computational homogenization analysis.

Table 8. Calibrated constitutive parameters for BM.

Material	W	k	n	ε_0	a	b	f_c	f_f	f_c^*	f_f^*
XS355A1B	0.9	836.2	0.1460	0.0095	598.2	549.9	0.0645	0.10	—	—
XS355A2B	0.9	772.7	0.1400	0.0068	563.3	511.8	0.0350	0.05	0.0350	0.05
XS355A3B	1.0	750.0	0.1400	0.0336	473.3	520.7	0.0350	0.05	0.0300	0.05
XS500A1B	0.8	738.1	0.0635	0.0150	508.1	595.8	0.1120	0.15	—	—
XS500A2B	0.6	696.0	0.0240	-0.0041	763.0	615.4	0.1290	0.15	0.0900	0.10
XS500A3B	0.7	851.4	0.0631	-0.0022	739.0	667.0	0.0760	0.10	0.0700	0.08
XS700A1B	0.1	942.9	0.0216	-0.0066	1237.4	834.6	0.0990	0.15	—	—
XS700A2B	0.1	919.0	0.0200	-0.0070	1293.2	816.7	0.0500	0.10	—	—
XS700A3B	0.1	997.2	0.0324	-0.0051	1052.0	853.4	0.0482	0.05	0.0706	0.08
S355t5B	0.8	801.5	0.1400	0.0151	557.4	539.4	0.0267	0.05	—	—
S355t8B	1.0	785.4	0.1400	0.0142	549.0	527.6	0.110	0.15	0.0600	0.08
S500t8B	0.9	757.1	0.0626	0.0196	493.2	616.6	0.123	0.15	0.0900	0.10

Table 9. Calibrated constitutive parameters for HAZ.

Material	k_0	Q	β_0	f_c	f_f	f_c^*	f_f^*
S355t5H	480.7	274.7	4.26	0.0116	0.05	—	—
S355t8H	481.0	285.1	4.03	0.0329	0.05	0.0186	0.05
S355t10H	459.5	191.6	13.89	0.0280	0.05	0.0550	0.10
S500t4H	552.0	191.6	8.33	0.0094	0.05	0.0250	0.05
S500t8H	363.3	336.7	17.25	0.0145	0.05	0.01447	0.05
S500t10H	578.6	207.2	8.68	0.0226	0.05	0.0150	0.05
S700t5H	627.7	355.7	5.28	0.0165	0.05	0.0470	0.05
S700t8H	598.6	205.0	10.47	0.0337	0.05	—	—
S700t10H	661.0	179.4	13.59	0.0177	0.05	—	—

A given VVF corresponds to a range of equivalent plastic strain instead of a unique value. An iteration analysis is conducted based on the RVE model to find the relationship between the range of the accumulated initial hardening strain and a specific VVF. The BM of the XS700A2 chord, denoted XS700A2B, is employed here for illustration. First, the original true stress-strain relationship is used in the RVE model with 0.1% VVF. For the model loaded with a minimum ($\alpha_2 = 0.1$) stress triaxiality, the equivalent plastic strain and VVF at the yield point are 0.062% and 0.258%, respectively. The model loaded with a maximum ($\alpha_2 = 1.2$) stress triaxiality has a 0.00382 equivalent strain and 0.343% VVF at the yield point. Comparing the results of the two models, VVF has a limited variation while the equivalent strain shows a significant difference. Hence, an RVE model with 0.3% VVF, which is approximately the average of two VVFs at the yield point (0.258% and 0.343%), is created for the second step analysis. As 0.062 and 0.00382 are the maximum and minimum equivalent plastic strains that may appear in the material with 0.3% VVF, the strains are used as the initial hardening strain (see Figure 11) to modify the original true stress-strain relationship. Note that the maximum and minimum initial hardening strains are slightly adjusted within the varying range

to have simple numbers. In addition, the average of the maximum and minimum initial hardening strain is used to generate a moderate constitutive model. The three modified stress-strain relationships are used in the second step analysis.

The model using the stress-strain relationship modified by the maximum initial hardening strain has the highest equivalent strain at the yield point under the $\alpha_2 = 0.1$ loading condition, while the model using the minimum-strain modified stress-strain relationship has the lowest equivalent yield strain under the $\alpha_2 = 1.2$ loading condition. VVF of these two models at the yield point shows a slight difference (0.554% and 0.663%). The average of two VVFs (approximately 0.6%) is used to create the RVE model for the third step. Similar to the first step, the original stress-strain relationship is modified using the accumulated initial hardening strain, which is the sum of maximum (or minimum) initial hardening strains. Again, a moderate modified constitutive model is created using the average of the maximum and minimum accumulated initial hardening strains.


The iteration analysis is conducted up until models with an 11% VVF. In the last several steps (VVF from 7% to 11%), a minimum 0.01 and maximum 0.04 hardening strain increment is obtained for every 1% VVF increment. Hence, the modified stress-strain relationship is estimated for models with a 15%, 20%, and 25% VVF concerning the calculation efficiency. The used accumulated initial hardening strains ($\Delta\varepsilon_1$, $\Delta\varepsilon_m$, $\Delta\varepsilon_h$) for all RVE models are presented in Table 4. Note that the same combinations of VVF and the accumulated initial hardening strain are used for other materials, as a similar result is observed in XS355A3B and S700t10H (HAZ of S700t10).

Yield surface parameters (q_1 and q_2)

An example of the RVE simulation result concerning a 5% VVF, a 0.07 accumulated initial hardening strain, and the Swift model extrapolation is presented in Figure 12. The

Table 10. Employed material for X-joint analysis.

X-joint	Chord		Brace		WM
	BM	HAZ	BM	HAZ	
XS355A1	XS355A1B	S355t8H	S355t5B	S355t5H	S355t8W
XS355A2	XS355A2B	S355t10H	S355t8B	S355t8H	S355t8W
XS355A3	XS355A3B	S355t8H	XS355A3B	S355t8H	S355t8W
XS500A1	XS500A1B	S500t8H	S500t8B	S500t8H	S700t8W
XS500A2	XS500A2B	S500t10H	S500t8B	S500t8H	S700t8W
XS500A3	XS500A3B	S500t4H	XS500A3	S500t4H	S700t8W
XS700A1	XS700A1B	S700t8H	XS700A3B	S700t5H	S700t8W
XS700A2	XS700A2B	S700t10H	XS700A3B	S700t5H	S700t8W
XS700A3	XS700A3B	S700t5H	XS700A3B	S700t5H	S700t8W

**Figure 15.** Failure modes of S355 X-joints. (a) XS355A1 ($\beta = 0.25$, CFF&PSF). (b) XS355A2 ($\beta = 0.88$, BF). (c) XS355A3 ($\beta = 1$, CSWF). (d) XS355A1-FE. (e) XS355A2-FE. (f) XS355A3-FE.

equivalent stress-strain relationship is used to characterise the yielding of the RVE model. When the slope of the curve decreases to 1% of the initial elastic stiffness, the point is considered the yield point. Figure 12(b) illustrates the pressure dependence of the yield surface, where the von Mises yield stress decreases with the increase of the mean stress.

The Mises stress, the mean stress, VVF, and the equivalent plastic strain at the yield point of all RVE models are used for determining the yield surface parameters q_1 and q_2 . According to the original GTN model,

q_3 equals $q_1^2 \cdot f^*$ and σ_y in equation (1) are VVF of the RVE model and the flow stress corresponding to the equivalent plastic strain according to the input data of the true stress-true plastic strain relationship, respectively. Substituting the variable values obtained from one RVE model into equation (1), an error could be calculated using a specific combination of q_1 and q_2 . The errors from all RVE models, including different VVFs, accumulated initial hardening strains, and α_2 values, are used to calibrate a constant q_2 using the least-squares method. Based on the determined q_2 , the sum of errors from models with different α_2 values

but the same VVF and accumulated initial hardening strain is used to identify q_1 , where a minimum sum of errors is obtained. The calibrated results for XS700A2B are presented in Table 5.

Fritzen et al. (2012) found that q_1 decreases with an increasing VVF and a constant q_2 . An expression correlating q_1 and VVF proposed by Yan et al. (2021b) is adopted in this work, as presented in equation (14).

$$q_1 = A \cdot f^B \tag{14}$$




Figure 16. Load-displacement relationship of S355 X-joints.

where A and B are two constitutive parameters determined by fitting the data presented in Table 5. It is very time-consuming to conduct the computational homogenization analysis for all materials involved in the X-joints, considering the number of RVE models. Hence, the materials with a similar strain hardening behaviour use the same A, B, and q_2 parameters. Figure 13 presents two examples of the materials with a similar strain hardening behaviour, (a) for BM and (b) for HAZ. The engineering stress is normalised by dividing the ultimate strength to compare the hardening behaviour of materials with different strengths. It can be seen that the curves in each diagram are almost identical until the ultimate strength point, where the extrapolation starts. BM and HAZ are sorted into four and two categories by visually inspecting the curves' shape, respectively. The analysed material and the material with a similar hardening behaviour are presented in Table 6. Note XS700A3B and S700t10H represents BM of XS700A3 chord and HAZ of S700t10, respectively.

The determined values of A, B, and q_2 are presented in Table 7. L, S, and V denote the linear, Swift, and Voce models, respectively. The undamaged true stress-strain relationship of BM can be generated using a weighting factor based on the Swift model and the linear model, as shown in equation (12). Accordingly, the constitutive




Figure 17. Failure modes of S500 X-joints. (a) XS500A1 ($\beta = 0.45$, CFF&PSF). (b) XS500A2 ($\beta = 0.87$, BF). (c) XS500A3 ($\beta = 1$, BF). (d) XS500A1-FE. (e) XS500A2-FE. (f) XS500A3-FE.

parameters (A, B, and q_2) can also be determined using the same weighting factor, as reported in (Yan et al., 2021b).

Fracture parameters (f_c and f_f)

The undamaged true stress-strain relationship is used in the coupon specimen analysis. The pressure-dependent yield surface of the GTN model is realised by the porous metal plasticity in ABAQUS. A user subroutine VUSDFLD, as introduced in (Yan et al., 2021b), is used to consider the

relationship between q_1 and VVF. The initial VVF f_0 is 0.001, resulting in a 0.999 relative density.

Figure 14(a) presents the engineering stress-strain relationship of XS700A3B. The solid black line is the experimental result. The results of FE1, FE2, and FE3 are extracted from the FE model with a 0, 0.1, and 0.2 weighting factor referring to equation (12), respectively. The FE model with a 0.1 weighting factor fits the experimental result best. The VVF contour plot of the half FE model at the failure point, where the load decreases sharply, is presented in Figure 14(b). It can be seen that the highest VVF appears at the centre of the cross-section, indicating the fracture initiates from the centre. The maximum VVF is taken as f_c . The value of f_f is determined based on a trial-and-error process by varying f_f . Figure 14(c) compares the experimental and the FE results, where FE2-1, FE2-2, and FE2-3 use 0.05, 0.1 and 0.15 f_f respectively. The model FE2-1 with a 0.05 f_f fits the experimental result best, although a minor difference could be observed among all three FE results. Note that the FE model with an f_f smaller than the proposed value would not notably influence the stress-strain relationship obtained from the FE result. Hence, an f_f which is maximally 0.05 larger than f_c is adopted in this study. The parameters calibrated for BM (referring to equation (10)) and HAZ




Figure 18. Load-displacement relationship of S500 X-joints.




Figure 19. Failure modes of S700 X-joints. (a) XS700A1 ($\beta = 0.42$, CFF&PSF). (b) XS700A2 ($\beta = 0.5$, BF). (c) XS700A3 ($\beta = 0.86$, PSF). (d) XS700A1-FE. (e) XS700A2-FE. (f) XS700A3-FE.

(referring to equation (9)) are summarized in Table 8 and Table 9, respectively.

Finite element analysis of X-joints

Heat-affected zone exists in both the brace and the chord of X-joints. The constitutive model of the HAZ that was developed for the butt-welded short tube is also used for modelling the HAZ in the X-joint. The model varies according to the thickness of the profile. The WM constitutive model is obtained from the milled welded coupon tests. The stress-strain relationship of WM extracted from DIC results is




Figure 20. Load-displacement relationship of S700 X-joints.

extrapolated using the Swift model. The same WM constitutive model is used for S500 and S700 joints, as the same electrode was used for welding. As coupon tests were not conducted for the brace, the material property of the brace refers to BM of the chord and the welded short tubes, according to the thickness. The employed materials for the X-joint simulation are summarized in Table 10, and the corresponding undamaged true stress-true plastic strain relationships are shown in Appendix A. The 1 mm C3D10 element is used at the possible fracture regions (HAZ, WM, BM close to HAZ) for joints with $\beta > 0.85$. Since the fracture parameters are closely related to the element volume, the values of f_c and f_t are adjusted for coupon models with 1 mm C3D10 element following the calibration procedure presented in Fracture parameters (f_c and f_t). The adjusted values are shown as f_c^* and f_t^* in Table 8 and Table 9.

The failure mode and the load-displacement relationship of X-joint FE models are compared to the experimental results in Figures 15 to 20. The predicted load-displacement relationships show a good agreement with the experimental results, although the resistance of FE results is slightly lower than the experiments at the plastic stage, which might be due to the pessimistic assumption of the constitutive model of the corner region in the cold-formed RHS. The material in the corner region has higher strength but lower ductility than the material in the flat region (Wang et al., 2017; Wilkinson, 1999). The absence

Table II. Comparison of FE and experimental ultimate resistances.

	A1			A2			A3		
	EXP (kN)	FE (kN)	FE/EXP [-]	EXP (kN)	FE (kN)	FE/EXP [-]	EXP (kN)	FE (kN)	FE/EXP [-]
XS355	546	555	1.02	1964	1911	0.97	1344	1355	1.01
XS500	897	919	1.02	2181	2020	0.93	1713	1647	0.96
XS700	875	793	0.91	769	780	1.01	952	910	0.96




Figure 21. Fracture surface in the experiment and FEA of XS700A1. (a) Fracture surface in experiment. (b) Fracture surface in FEA. (c) A sketch of the fracture surface.




Figure 22. Fracture surface in experiments and FEA of XS700A2. (a) Fracture surface in experiment. (b) Fracture surface in FEA. (c) A sketch of the fracture surface.

of the corner material model may also result in a more significant deformation at the ultimate load since the stress concentration is relaxed at the corner region, where the low ductility may lead to a premature fracture. For a joint with a small β , the deformation is mainly due to the deflection of the chord surface, and the role of the corner in the overall behaviour of the joint is less pronounced. For a joint with a large β , the corner region acts more strongly in the load transfer, and the material at the corner undergoes more severe yielding that may lead to failure. Consequently, omitting the work-hardening of the corner region in the material model may have a stronger influence on the FE results for joints with larger β values. In addition, the FE model is only one-quarter of the specimen, and symmetric boundary conditions are applied. The deformation obtained from the FE model may be larger than the experiments, as the fracture appears only on a weaker side of most joints.

The ultimate resistances obtained from FE models are compared to the experiments in Table 11. The FE/EXP resistance ratio varies from 0.91 to 1.02, with an average value of 0.98. It is worth mentioning that the resistance of PSF is well predicted even though the shear damage model is not considered in the employed GTN model. The same finding was reported by Liu et al. (2018), where the proposed shear-modified GTN model can improve the results of the fracture propagation but not the ultimate resistance and the corresponding deformation. The reason for the accurate prediction on the ultimate resistance is that the Lode angle has limited influence on the fracture plastic strain under a high stress triaxiality (Bai and Wierzbicki, 2008; Cao et al., 2014; Huang et al., 2020; Ma et al., 2015). The stress triaxiality in the elements involved in fracture of four PSF models varies between 0.6 and 1.5. In addition, the number of elements in the FE model exposed to a shear stress state is very limited, which has a minor influence from a joint global behaviour perspective.

The fracture surface of all joints, except for XS700A1, is well predicted using the calibrated GTN damage model. Only XS355A3 had CSWF with an arc-shaped fracture. The FE predicted fracture has a similar shape but is slightly closer to the corner of the chord, which might be due to the absence of the constitutive model of the corner region.

Two orientations of the fracture surface for PSF were observed in the experiments. The fracture of XS355A1, XS500A1, and XS700A3 initiated at the weld toe and cut through the thickness of the tube (see Figure 15, Figure 17, and Figure 19), which is successfully predicted by the FE model. The fracture surface of XS700A1 propagated below the weld, as shown in Figure 21 (solid red line for the experiment and red dash line for the FE model), which fails to predict.

The fractures of all BF have the same orientation, as shown in Figure 14, Figure 16, and Figure 18. A detailed shape of the fracture surface is shown in Figure 22 (a). The normal direction of the fracture surface points out of the X-joint. As the fracture starts from the toe of the weld, the fracture involves HAZ and BM. The FE model successfully predicts the failure mode.

Conclusions and further research

The GTN damage model is implemented into the fracture simulation of welded cold-formed RHS X-joints. Based on the presented results, the following conclusions are drawn:

1. The computational homogenisation is conducted to calibrate the GTN yield-surface parameters (q_1 and q_2), considering the different combinations of the accumulated initial hardening strain and the VVF (f). Parameter q_1 is correlated to the VVF f using the power law, $q_1 = Af^B$, for a constant q_2 calibrated for different models shown in Table 7. All values of

- q_2 for different materials considered are close to 1. Parameter q_1 gradually decreases from 3 to 1.5 with an increasing f .
- The undamaged true stress-true strain relationship of the BM is generated using a weighting factor (W) based on the Swift model and the linear model. The weighting factor decreases with the increase of the steel grade, which is around 0.9, 0.7, and 0.1 for S355, S500, and S700 material, respectively. It indicates that the BM undamaged constitutive model gradually transfers from the linear model to the Swift model concerning an ascending steel grade. The HAZ material has a weaker post-necking strain hardening behaviour than BM. The Voce model is suitable for generating the undamaged constitutive model for all HAZ materials.
 - The damage of the element is sensitive to the value of the fracture parameter f_c . f_f has a minor influence on the failure process. The value of f_b , up to 5% larger than f_c , is validated in this study.
 - The calibrated GTN damage model for BM and HAZ could effectively predict the fracture-related failure modes: PSF, BF, and CSWF, of welded RHS X-joints in tension, although the material shear failure mechanism is not considered. Comparing the ultimate resistance of the FE models and the experiments (EXP), the FE/EXP ultimate resistance ratio varies from 0.91 to 1.02, with an average 0.98 ratio.
 - Two orientations of the PSF fracture surface are observed in experiments. The FE model successfully predicts the fracture cutting through the profile thickness of the chord, while the fracture propagated below the weld was not accurately predicted. The fractures of BF and CSWF are well predicted. Both BM and HAZ contributed to the fracture of BF. The predicted fracture shape of CSWF may be improved by considering the constitutive model of the corner material in cold-formed RHS tubes.
 - The main limitation of the employed GTN damage model is that the effect of the Lode angle on the material yield and failure criterion is not considered, although the predicted ultimate resistance fits the experiments well. It will be considered in future work and a generic FE model will be validated at various stress states. In addition, a constitutive model for the corner material of cold-formed RHS tubes, including BM and HAZ, should be established based on experimental and numerical studies. Using the validated corner material model, the FE model will be complete to evaluate the effect of high strength and low ductility of corner material on the joint mechanical behaviour.

Declaration of conflicting interests

The author(s) declared no potential conflicts of interest with respect to the research, authorship, and/or publication of this article.

Funding

The author(s) received no financial support for the research, authorship, and/or publication of this article.

ORCID iD

Rui Yan  <https://orcid.org/0000-0002-8495-1289>

References

- ABAQUS (2021) *ABAQUS Analysis User's Manual, 2021 Version*.
- Amraei M, Ahola A, Afkhami S, et al. (2019) Effects of heat input on the mechanical properties of butt-welded high and ultra-high strength steels. *Engineering Structures* 198: 109460. DOI: [10.1016/j.engstruct.2019.109460](https://doi.org/10.1016/j.engstruct.2019.109460)
- Amraei M, Afkhami S, Javaheri V, et al. (2020) Mechanical properties and microstructural evaluation of the heat-affected zone in ultra-high strength steels. *Thin-Walled Structures* 157: 107072. DOI: [10.1016/j.tws.2020.107072](https://doi.org/10.1016/j.tws.2020.107072)
- Bai Y and Wierzbicki T (2008) A new model of metal plasticity and fracture with pressure and Lode dependence. *International Journal of Plasticity* 24: 1071–1096. DOI: [10.1016/j.ijplas.2007.09.004](https://doi.org/10.1016/j.ijplas.2007.09.004)
- Becque J and Wilkinson T (2017) The capacity of grade C450 cold-formed rectangular hollow section T and X connections: an experimental investigation. *Journal of Constructional Steel Research* 133: 345–359. DOI: [10.1016/j.jcsr.2017.02.032](https://doi.org/10.1016/j.jcsr.2017.02.032)
- Björk T and Saastamoinen H (2012) Capacity of CFRHS X-joints made of double-grade S420 steel. In: *Tubular Structures XIV - Proceedings of the 14th International Symposium on Tubular Structures (ISTS)*, London, UK, 12–14 September 2012, 167–176. DOI: [10.1201/b13139-26](https://doi.org/10.1201/b13139-26)
- Cai W, Wang Y, Li G, et al. (2022) Comparative study on strength of TMCP and QT high-strength steel butt-welded joints. *Journal of Constructional Steel Research* 197: 107447. DOI: [10.1016/j.jcsr.2022.107447](https://doi.org/10.1016/j.jcsr.2022.107447)
- Cao T, Gachet J, Montmitonnet P, et al. (2014) A Lode-dependent enhanced Lemaitre model for ductile fracture prediction at low stress triaxiality. *Engineering Fracture Mechanics* 124–125: 80–96. DOI: [10.1016/j.engfracmech.2014.03.021](https://doi.org/10.1016/j.engfracmech.2014.03.021)
- Chen C, Chiew SP, Zhao MS, et al. (2019) Welding effect on tensile strength of grade S690Q steel butt joint. *Journal of Constructional Steel Research* 153: 153–168. DOI: [10.1016/j.jcsr.2018.10.009](https://doi.org/10.1016/j.jcsr.2018.10.009)
- EN 1993-1-12:2007 (2007) *Design of steel structures - part 1–12: additional rules for the extension of EN 1993 up to steel grades S700*.

- Fritzen F, Forest S, Böhlke T, et al. (2012) Computational homogenization of elasto-plastic porous metals. *International Journal of Plasticity* 29: 102–119. DOI: [10.1016/j.ijplas.2011.08.005](https://doi.org/10.1016/j.ijplas.2011.08.005)
- Feldmann M, Schillo N, Schaffrath S, et al. (2016) *Rules on High Strength Steel*. <https://op.europa.eu/en/publication-detail/-/publication/515285b0-c820-11e6-a6db-01aa75ed71a1/language-en/format-PDF/source-194823584>
- Huang X, Ge J, Zhao J, et al. (2020) A continuous damage model of Q690D steel considering the influence of Lode parameter and its application. *Construction and Building Materials* 262: 120067. DOI: [10.1016/j.conbuildmat.2020.120067](https://doi.org/10.1016/j.conbuildmat.2020.120067)
- Huang X, Wei C, Zhao J, et al. (2021) Fracture prediction of circular steel tubular X-joints using a Lode parameter enhanced cyclic void growth model. *Engineering Structures* 245: 112869. DOI: [10.1016/j.engstruct.2021.112869](https://doi.org/10.1016/j.engstruct.2021.112869)
- Kim J-H, Lee C-H, Kim S-H, et al. (2019) Experimental and analytical study of high-strength steel RHS X-joints under axial compression. *Journal of Structural Engineering* 145: 04019148. DOI: [10.1061/\(asce\)st.1943-541x.0002435](https://doi.org/10.1061/(asce)st.1943-541x.0002435)
- Lan X, Chan TM and Young B (2019) Structural behaviour and design of high strength steel RHS X-joints. *Engineering Structures* 200: 109494. DOI: [10.1016/j.engstruct.2019.109494](https://doi.org/10.1016/j.engstruct.2019.109494)
- Lan X, Chan TM and Young B (2021) Testing, finite element analysis and design of high strength steel RHS T-joints. *Engineering Structures* 227: 111184. DOI: [10.1016/j.engstruct.2020.111184](https://doi.org/10.1016/j.engstruct.2020.111184)
- Lee C-H and Kim S-H (2018) *Structural Performance of CHS X-joints Fabricated from High-Strength Steel*. DOI: [10.1002/stco.201800021](https://doi.org/10.1002/stco.201800021)
- Lee C-H, Kim S-H, Chung D-H, et al. (2017) Experimental and numerical study of cold-formed high-strength steel CHS X-joints. *Journal of Structural Engineering* 143: 04017077. DOI: [10.1061/\(asce\)st.1943-541x.0001806](https://doi.org/10.1061/(asce)st.1943-541x.0001806)
- Ling Y (2004) Uniaxial true stress-strain after necking. *AMP Journal of Technology* 5: 37–48.
- Liu J, Yan S and Zhao X (2018) Simulation of fracture of a tubular X-joint using a shear-modified Gurson–Tvergaard–Needleman model. *Thin-Walled Structures* 132: 120–135. DOI: [10.1016/j.tws.2018.07.054](https://doi.org/10.1016/j.tws.2018.07.054)
- Ma X, Wang W, Chen Y, et al. (2015) Simulation of ductile fracture in welded tubular connections using a simplified damage plasticity model considering the effect of stress triaxiality and Lode angle. *Journal of Constructional Steel Research* 114: 217–236. DOI: [10.1016/j.jcsr.2015.07.023](https://doi.org/10.1016/j.jcsr.2015.07.023)
- Metallic materials - Tensile testing - Part 1: Method of test at room temperature (ISO 6892-1:2019), 1 (2019).
- Mohan M and Wilkinson T (2022) Damage criterion approach to high-strength steel RHS truss joints. *Steel Construction*. DOI: [10.1002/stco.202100027](https://doi.org/10.1002/stco.202100027)
- Peng Y, Wu C, Gan J, et al. (2019) Characterization of heterogeneous constitutive relationship of the welded joint based on the stress-hardness relationship using micro-hardness tests. *Construction and Building Materials* 202: 37–45. DOI: [10.1016/j.conbuildmat.2018.12.218](https://doi.org/10.1016/j.conbuildmat.2018.12.218)
- Peng Y, Wu C, Gan J, et al. (2018) Determination of the local constitutive properties of the welded steel joints using digital image correlation method. *Construction and Building Materials* 171: 485–492. DOI: [10.1016/j.conbuildmat.2018.03.182](https://doi.org/10.1016/j.conbuildmat.2018.03.182)
- prEN 1993-1-8:2021 (2021) *Design of Steel Structures - Part 1-8: Design of Joints*.
- Swift HW (1952) Plastic instability under plane stress. *Journal of the Mechanics and Physics of Solids* 1: 1–18. DOI: [10.1016/0022-5096\(52\)90002-1](https://doi.org/10.1016/0022-5096(52)90002-1)
- Tvergaard V and Needleman A (1984) Analysis of the cup-cone fracture in a round tensile bar. *Acta Metallurgica* 32: 157–169. DOI: [10.1016/0001-6160\(84\)90213-X](https://doi.org/10.1016/0001-6160(84)90213-X)
- Tuominen N and Björk T (2017) *Capacity of RHS-Joints Made of High Strength Steels*. CIDECT Report 5BZ Final report.
- Voce E (1948) The relationship between stress and strain for homogeneous deformation. *Journal of the Institute of Metals* 74: 537–562.
- Wang J, Afshan S, Schillo N, et al. (2017) Material properties and compressive local buckling response of high strength steel square and rectangular hollow sections. *Engineering Structures* 130: 297–315. DOI: [10.1016/j.engstruct.2016.10.023](https://doi.org/10.1016/j.engstruct.2016.10.023)
- Wilkinson T (1999) *The Plastic Behaviour of Cold-Formed Rectangular Hollow Sections*.
- Xin H, Kisoensingh P and Veljkovic M (2021) Mechanical behaviour of welded high strength steel rectangular hollow section joints. *Engineering Failure Analysis* 125: 105410. DOI: [10.1016/j.engfailanal.2021.105410](https://doi.org/10.1016/j.engfailanal.2021.105410)
- Xin H and Veljkovic M (2021) Evaluation of high strength steels fracture based on uniaxial stress-strain curves. *Engineering Failure Analysis* 120: 105025. DOI: [10.1016/j.engfailanal.2020.105025](https://doi.org/10.1016/j.engfailanal.2020.105025)
- Yan R, El Bamby H, Veljkovic M, et al. (2021a) A method for identifying the boundary of regions in welded coupon specimens using digital image correlation. *Materials & Design* 210: 110073. DOI: [10.1016/j.matdes.2021.110073](https://doi.org/10.1016/j.matdes.2021.110073)
- Yan R, Mela K, El Bamby H, et al. (2022a) *Experimental Investigation on the Tensile Behaviour of Welded RHS High Strength Steel X-Joints (Under Review)*. Engineering Structures.
- Yan R, Mela K, Yang F, et al. (2022b) Equivalent material properties of the heat-affected zone in welded cold-formed rectangular hollow section connections (under review). *Thin-Walled Structures*.
- Yan R, Xin H and Veljkovic M (2020) *Identification of GTN Damage Parameters as a Surrogate Model for S355*, 582–589. DOI: [10.3850/978-981-11-0745-0_066-cd](https://doi.org/10.3850/978-981-11-0745-0_066-cd)
- Yan R, Xin H and Veljkovic M (2021b) Ductile fracture simulation of cold-formed high strength steel using GTN damage model. *Journal of Constructional Steel Research* 184: 106832. DOI: [10.1016/j.jcsr.2021.106832](https://doi.org/10.1016/j.jcsr.2021.106832)
- Yan R, Xin H, Yang F, et al. (2022c) A method for determining the constitutive model of the heat-affected zone using digital image correlation. *Construction and Building Materials*. DOI: [10.1016/j.conbuildmat.2022.127981](https://doi.org/10.1016/j.conbuildmat.2022.127981)

Appendix




Figure A1. Undamaged true stress-true plastic strain relationships for X-joint simulations.