

Architecture & Engineering: 1 Million Homes

# UNIVERSAL MODULAR BUILDING

Axel Beem 4283015

## Tutors

Design: Mauro Paraviccini  
Building Technology: Gilbert Koskamp  
Research: Pieter Stoutjesdijk



# Two fundamental challenges in the built environment



## 1. There is a large and long lasting need for new homes.

- In the Netherlands, we need **1.000.000 new homes by 2030.**
- Globally, we need **2.000.000.000 new homes by 2100.**





## 2. There is a drastic and urgent need for reduced pollution from the building industry.

- The building industry currently causes around 50% of man-made climate change.<sup>1</sup>
- Concrete and steel production together are responsible for 15% of global anthropogenic CO2 emissions.<sup>2</sup>

<sup>1</sup> [https://www.worldgbc.org/sites/default/files/UNEP%20188\\_GABC\\_en%20%28web%29.pdf](https://www.worldgbc.org/sites/default/files/UNEP%20188_GABC_en%20%28web%29.pdf)

<sup>2</sup> [https://www.researchgate.net/publication/302061863\\_Long-term\\_model-based\\_projections\\_of\\_energy\\_use\\_and\\_CO2\\_emissions\\_from\\_the\\_global\\_steel\\_and\\_cement\\_industries](https://www.researchgate.net/publication/302061863_Long-term_model-based_projections_of_energy_use_and_CO2_emissions_from_the_global_steel_and_cement_industries)







# Opportunity 1: Engineered Wood

**CLT**



**Glu-lam**




**LVL**




- Strong & Lightweight
- Climate-friendly production (low emissions & wood absorbs CO<sup>2</sup> during growth)
- High workability (CnC milling, high precision, automated production)

## Opportunity 2: ‘Low-hanging fruit’



Most buildings we make have very simple structures that could easily be made out of a system of some kind.








## Construction materials dominate resource consumption

Consumption in gigatonnes



# **The Design Assignment**

## **1. Design a Modular Reusable Building System prototype.**

- Disassemblable
- Flexible in life (e.g. changable inner walls)
  - Allows freedom of design
- Useable in conjunction with 'normal', custom building elements
  - Engineered wood as main body

## **2. Use system to design two buildings in drastically different contexts**

- Show the system can adapt to different climates, architectural cultures and local problems.
  - Chosen locations are Amsterdam, the Netherlands and Jakarta, Indonesia



## **Cornerstones**

### **1. System elements are directly reusable**

- assembly**
- damage**
- transport**
- storage**
- etc..**

1. Fill in product context profile & pairwise comparison to determine category weights

Pairwise Comparison Chart (PCC)		Tool Complexity Workspace Accessibility Product placement/removal Labour intensiveness Connectivity Damage Functional Reusability End of cycle potential Transport and storage Required operator qualifications																	Rating score		Percentual score	
Tool Complexity			5	1/2	4	1/2	6	1/2	1/7	1/7	1/4								17,0			7,8%
Workspace Accessibility	1/5			1/3	1/4	1/5	3	1/5	1/7	1/7	1/5								4,7			2,1%
Product placement/removal	2	3			6	3	7	3	1/3	3	5								32,3			14,8%
Labour intensiveness	1/4	4	1/6			1/5	3	1/6	1/7	1/6	1/5								8,3			3,8%
Connectivity	2	5	1/3	5			6	1/3	1/5	1/4	2								21,1			9,7%
Damage	1/6	1/3	1/7	1/3	1/6			1/7	1/7	1/7	1/4								1,8			0,8%
Functional Reusability	2	5	1/3	6	3	7			1/5	1/5	2								25,7			11,8%
End of cycle Potential	7	7	3	7	5	7	5				2	5							48,0			22,0%
Transport and storage	7	7	1/3	6	4	7	5	1/2				3							39,8			18,2%
Required operator qualifications	4	5	1/5	5	1/2	4	1/2	1/5	1/3										19,7			9,0%

2. Fill in scoring tables for different categories and sub-categories (e.g. (dis)assembly, reusability in new designs)

Tool Complexity (Assembly)	Rating
Tools are not required; task is accomplished by hand	9
Common hand tools are required	7
Power tools are required	6
Special tools are required	5
Significant time delay	-2
Special care/techniques are needed	-1

Workspace accessibility	Rating
Mounting can be done with hardly any space required (< 5 cm)	9
Mounting requires some space for hands or small hand tools (< 20 cm)	7
Mounting requires significant space for hand or powered tools	5
Special care/tools/techniques are needed	-1
Blind assembly/disassembly	-1
Significant time delay	-1
One product have to be removed to access the area	-1
Multiple products have to be removed to access the area	-2

3. Combine all scores and weigh according to pairwise comparison

				Perfect example		Product 1		Product 2		Product 3		Product 4		Product 5		Product 6	
	Factor	%		Rating	Score	R	S	R	S	R	S	R	S	R	S	R	S
Tool Complexity	17,0	7,8%		9	153,3	9	153	9	153	8	136	8	136	8	136	8	136
Number of fastener types	17,0			9	153,3	9	153	9	153	7	119	7	119	7	119	7	119
Workspace Accessibility	4,7	2,1%		9	42,0	9	42	9	42	7	33	7	33	7	33	7	33
Product placement/removal	32,3	14,8%		9	291,0	9	291	9	291	7	226	7	226	7	226	7	226
Labour intensiveness	8,3	3,8%		9	74,6	9	75	8	66	9	75	9	75	9	75	9	75
Connectivity	21,1	9,7%		9	190,1	9	190	9	190	9	190	9	190	9	190	9	190
Damage	1,8	0,8%		9	16,4	8	15	8	15	8	15	8	15	8	15	8	15
Functional Reusability	25,7	11,8%		9	231,6	7	180	7	180	7	180	7	180	7	180	7	180
End of cycle potential	48,0	22,0%		9	432,0	1	48	1	48	1	48	4	192	4	192	4	192
Transport and storage	39,8	18,2%		9	358,5	9	359	9	359	9	359	9	359	9	359	9	359
Required operator qualifications	19,7	9,0%		9	177,6	9	178	9	178	9	178	9	178	9	178	9	178
Space needed					2120,4		###		###		###		###		###		###
					Maximum Score		100		79,4		79,0		73,5		80,3		80,3





4. Compare final- and sub-scores to gain insight about the product’s reusability

## **Cornerstones:**

### **1. System elements are directly reusable**

- assembly**
- damage**
- transport**
- storage**
- etc..**

### **2. System must give user FREEDOM OF DESIGN**



- Loss of identity
- Loss of sense of belonging
- Uninspiring / Depressing











## **Cornerstones**


### **1. System elements are directly reusable**

- assembly**
- damage**
- transport**
- storage**
- etc..**


### **2. System must have Freedom of Design**

### **3. Climate-friendly production (WOOD!)**


### **4. Prefabrication (efficiency, digital & smart production)**








Core of building made  
entirely out of system elements



Small amount of custom additions



Final result that is demountable and for  
the most part directly reusable


SYSTEM DESIGN


# System design: Existing Solutions




**X-rad system by ROTHOBLAAS**































































# FLOOR ELEMENT

A

## VARIABLES

The floor elements have three variables. The first variable is the span, which varies according to standard grid units of 1500 mm (V-G).

The second variable is the width, which also varies according to V-G.

The third variable is the thickness, which varies according to a number of standard measurements (V-S) based on both span and load. In this case the thickness is 220+50, with 220 mm of the thickness being load-bearing and the bottom 50 mm facilitating attachment points.

B

## PRIMARY ATTACHMENT POINTS

At the bottom side, each corner has milled-in space where the steel interfaces are placed to connect the floors to walls or beams.

These interfaces can vary in height to either heighten or lower the floor elements as required for the design.

C

## SECONDARY ATTACHMENT POINTS

Similar to the beam elements, the floor elements have a bottom layer of 50 mm non-loadbearing CLT with milled-in slits and pre-drilled holes.

These serve as attachment points for add-ons that can fulfill a variety and multiplicity of functions: sound insulation, fire proofing, electrics, ventilation and lowered ceiling (additional height).

D

## SECONDARY ATTACHMENT POINTS

On the top side, the floor elements have pre-drilled holes according to a simple grid of 150 x 150 mm.

These holes serve as the attachment points for both floor add-ons (extra height, sound insulation, weight) and the 'footprints' of walls.

These elements are connected via friction-fit steel pins to be completely remountable.

E

## VARIANTS

Depicted a several variants of the floor element, differing in width and span.

Notable is the bottom variant, which has double width and spacing in the middle for columns in the system grid. This variant makes use of the property of CLT where it can bear loads in both perpendicular directions, and only needs to be secured at the corners.

A

**Topside Add-on (PRE-FAB)**

Additional Height, Weight, Sound insulation. Variable according to building needs. Pre-drilled holes as attachment points for wall foot-prints.

B

**Floor Element (PRE-FAB)**

According to blueprint.

C



**Bottomside Add-on (PRE-FAB)**

Additional height, sound insulation, electrics and installations. Slid unto the bottom of the floor element and secured with horizontal friction fit pins.


D

**Ceiling Finish**


Fire-proofing. Finish. Added on-site. Variable.






































































# DESIGN SHOWCASES





## PRIMARY SHOWCASE

THE NETHERLANDS,  
AMSTERDAM,  
NIEUW WEST,  
OSDORPPLEIN.



## SECONDARY SHOWCASE

INDONESIA,  
JAKARTA,  
CENKARENG,  
RAWA BUAYA.





**Locational differences:**

- 1. Climate**
- 2. Architectural culture**
- 3. Local problems**
- 4. Future developments**





# AMSTERDAM


**Local challenge:** Dutch housing crisis, lack of affordable and fitting home, especially for starters

**Target Group:** Starters & Starting families
























**HEROS 02<sup>B</sup>**

- 18 serviced appartments
- Internationale kenniswerkers
- Verblijfsduur 2 - 6 maanden

**HEROS 02<sup>A</sup>**

- 51 huurappartementen
- Sociaal segment
- Alleenstand, samenwonend, kleine gezinnen

**HEROS 01**

- 49 huurappartementen
- Hoog segment
- hogere inkomensgroepen, urban professionals, tweeverdieners en 55-plus

**HEROS 03**

- 49 huurappartementen
- Midden segment
- Senioren, stedelijke gezinnen, young professionals

**PARKEREN**

- 221 inpandige parkeerplaatsen
- bewoners en bezoekers

**WINKELS**

- 5.100 m<sup>2</sup>
- Supermarkt, winkels

**ZORGCENTRUM**

- 1.400 m<sup>2</sup>


**HORECA**

- 300 m<sup>2</sup>













































**Old Footprint: 1.500 m<sup>2</sup>**




**New Footprint: 2.000 m<sup>2</sup>**



**Old floor space: ~2.200 m<sup>2</sup>**


- Heavyweight concrete construction
- Two double height floors



**New floor space: max ~13.500 m<sup>2</sup>**



- Lightweight wooden construction
- Six floors on old foundation, nine on new foundation





Amsterdam: Program of Requirements


Dwellings & storage: 2200m²






### Type A

Couple  
30 - 40m<sup>2</sup>




### Type B

3-person household  
55- 60 m<sup>2</sup>




### Type C

4-person household  
70 - 75 m<sup>2</sup>








### Loss of individual (spatial) value on dwelling scale

- Smaller dwellings
- Fewer possibilities for social interactions, events, leisure, in private dwelling





### Maximize efficiency available space

- Remove dedicated circulation space
- Integrate storage
- Maximize feeling of spaciousness






**Opportunity: Introduce community (spatial) value on building scale**

- Bring back lost values in shared environment.
- Sharing saves money & brings people together
- Encourages feeling of community & social interaction



BUILDING DESIGN









# CHALLENGE 1: DEALING WITH THE EXISTING





















































































































## CHALLENGE 2: FREELY PLANNABLE FLOOR PLANS





























## DETAIL G

PREFAB / ON-SITE



SYSTEM / CUSTOM



**GFRP 3x 12,5 mm**

Outer layer used as functional finish layer

**Studs / Rockwool, 80m**

Sound insulation

**GFRP 3x 12,5 mm**

**Rockwool 20 mm**

Decoupling layer

Sound insulation

**GFRP 3x 12,5 mm**

**Studs / Rockwool, 80m**

Sound insulation

**GFRP 3x 12,5 mm**

**Interior wall connecting foot**

Thin steel plate integrated on the bottom of pre-fab interior wall elements. Connects to pre-fab floor via disposable wooden interface

**Elastomer Joint**

Decoupling element between wall and floor


**Interior wall wooden footprint / interface**

Custom-measured wooden footprint that forms the disposable / non-reusable connecting element between system wall and system floor elements. Attached to floor via steel friction-fit pins. Attached to wall via simple screws.


**Steel pins**

Friction-fit / demountable connection between wooden footprint and floor element. Goes through infill layer into CLT floor element.






































# CHALLENGE 3: LEVEL DIFFERENCE & CUSTOM ELEMENTS







**DETAIL E**



**Extra large custom floor edge closer**

Constructed with simple wood frame construction.  
Custom measurements to accommodate floor level difference.  
Space for pipes and cables.


**Floor level difference**

Facilitates level transition between dwellings and roof terrace  
See Detail E'

**Custom ceiling add-on**

Placed at the level difference, bottom floor elements have special custom ceiling add-ons (Fire protection, sound insulation) that provide full encapsulation of constructive elements.

**DETAIL E'**



**Standard Glu-Lam Post**

450x450x3200 mm  
Integrated tubular steel interfaces at top and bottom side to connect elements.

**Custom Post-Beam Steel Interface**

Executed as a single element with two different height levels for beams.  
Slid over topside of post interfaces before new constructive layer is added.

**Custom Post-Floor Steel Interface**


Executed as a single element with two different height levels for floors.  
Attached to post interface

**Standard Glu-Lam Beams**


(<)9000 mm span, 500 mm height (450+50)  
Attached to steel interfaces with 6 remountable bolts.




PREFAB / ON-SITE



SYSTEM / CUSTOM




DETAIL D




- Terrace finish, wooden deck, 18mm
- Wood frame, 100 + 40mm
  - Constructive element opening at facade side to allow water to flow to drainage points
- Waterproof membrane
- Thermal Insulation (EPS), 250mm
  - 10/1000 height gradient to facilitate water drainage
  - Water drainage integrated in layer
  - Seperate closed-off water drainage for green roof segments
- Vapor barrier
- Downspout coupling point
  - Downspout is integrated in pre-fab facade elements, extended to roof/terrace on-site



































FLOOR 03 ▾

SPACE 1 ▾



Give your event a name!...

FROM ▾

12:30

12:45

13:00

TO ▾

14:15

14:30

14:45

TO ▾

BIRTHDAY PARTY

DINNER

OTHER...

If it is an open event, give the community a short description! ...



## UPCOMING COMMUNITY EVENTS

Saturday 13:00 - 17:00 **F03 SPACE 1**



**TAMAR'S BIRTHDAY PARTY!!**  
ALL KIDS INVITED! :D



Ages 8-11, baking cookies for lunch!

Sunday 20:00 - 24:00 **F03 SPACE 1**



**BOARD GAME NIGHT Edition 23!**  
Catan, Monopoly, Risk. Usual rules.  
No more cheating, brandon! :p  
Different floor this time!



## PAST WEEK

Sunday 20:00 - 24:00 **F01 SPACE 3**



**BOARD GAME NIGHT edition 22**  
This week: only risk! Bring your best game!!



**Evan Raaphorst**  
BRANDON CHEATED FOR SURE!!



**Brandon Bekker**  
Great game guys, close one :^)

Sunday 20:00 - 24:00 **F03 SPACE 1**



**BOARD GAME NIGHT edition 21**  
This week: only risk! Bring your best game!!



**Evan Raaphorst**  
BRANDON CHEATED FOR SURE!!



**Brandon Bekker**  
Great game guys, close one :^)

















## CHALLENGE 4: CUSTOM STRUCTURE




PREFAB / ON-SITE



SYSTEM / CUSTOM



DETAIL C



**Wood frame construction**

Balcony-bearing construction  
Custom element  
Finished with Derako demountable  
wood facade system  
Anchored to facade for stability

**Wooden Interface construction**

Custom wooden construction  
Connects custom balcony construction  
to building system standard beam  
Constructed on-site

**Terrace finish, wooden deck, 18mm**

**Wood frame, 100 + 40mm**

Constructive element  
Lower frame aligned with insulation height  
gradient to  
allow water drainage

**Waterproof membrane**

**Thermal Insulation (EPS), 250mm**

10/1000 height gradient to facilitate water  
drainage

Water drainage integrated in layer


**Vapor barrier**

**Glu-lam 9m System beam**


Standard system element  
Thicker Variant compared to beams that do not  
bear balcony load

50






















# MODULARITY ANALYSIS






Amsterdam: Construction




**EXCLUDING**

- Foundation
- Concrete elevator cores
- Pergola construction
- Greenhouse construction







Amsterdam: Interior Walls











Amsterdam: Building Envelope












Amsterdam: Building Envelope





# JAKARTA

**Local challenge:** City flooding in 20 - 30 years, but big demand for housing

**Target Group:** Former rural migrants















SHOWCASE: JAKARTA

















































# MODULARITY ANALYSIS







Jakarta: Construction

**EXCLUDING**


Foundation  
Elevator









Jakarta: Interior Walls








Jakarta: Building Envelope







PREFAB / ON-SITE



SYSTEM / CUSTOM




Jakarta Balcony Joint






# CONCLUSION










# AMSTERDAM




# JAKARTA




Amsterdam: Construction




Amsterdam: Interior Walls




Amsterdam: Building Envelope



Jakarta: Construction







Jakarta: Interior Walls



Jakarta: Building Envelope






- Lower average pollution during production (wood > concrete/steel)
- Only have additional production when elements reach End of Life
- Vast and exponentially growing reduction of emissions over time

- Production more expensive (more complex elements)
- Linear costs to harvest materials
- Exponentially growing profit over time, breaking even at the second building cycle













SOURCE: <https://www.theglobeandmail.com/arts/art-and-architecture/article-can-wood-build-the-future-of-wood-well-see/>

CONCLUSION







BOOKLET




# SITUATION & FLOOR PLANS







































DETAILS



DETAIL A




Custom floor edge closer  
Only for floor elements that support facade  
via steel interface

- Stucco, finishing layer, 2mm
- Gypsum fibre board 2x, 30mm
- Fire protection
- Functional finishing layer
- Vapor barrier
- Rockwool, 300mm
- Thermal insulation
- Sound insulation for exterior sound
- Waterproof membrane
- Ventilated cavity, 35mm
- Aberson A-brick system: metal sheet , 5mm protrusions to attach brick faces
- Aberson A-brick system: brick faces, 25mm demountable ceramic facade system


Floor-Facade Connection  
Vertical space is provided to ease appliance of vapor barrier, see details A & A'

DETAIL A-Horiz



Floor-Facade interface  
At the top side of the facade elements, the interface spreads the entire width to provide freedom of placement and strong construction. Attached with steel bolts, easily disassemblable.


DETAIL A-Horiz'



Floor-Facade interface  
At the bottom side of the facade elements, the interfaces don't spread the entire width and provide space to seal the seams between separate elements on-site.



**DETAIL B**




**Lightweight steel frame**  
Greenhouse construction  
Attached to construction with method comparable to detail X

**Custom roof edge construction**  
Non-system roof edge, wood frame construction  
Attached to facade elements via disposable wooden interfaces  
**Downspout coupling piece**  
Custom piece to couple the pre-fab water drainage from roof and facade elements

**Greenhouse flooring, wooden deck, 18mm**  
**Gravel, 150mm**  
Water drainage  
Extra weight for construction  
Sound insulation  
Integrated water system for greenhouse units  
**Waterproof membrane**  
**Timber, 18mm | PREFAB**  
Roof construction topping layer  
**Thermal Insulation (EPS), 250mm | PREFAB**  
Water drainage integrated  
**Vapor barrier | PREFAB**  
**CLT, 360mm**  
Constructive element  
Extra thickness to bear load of greenhouse  
**Rockwool, 40mm**  
Additional sound insulation  
**Gypsum fibre board double layer, 30mm**  
Fire protection  
Functional finishing layer  
**Stucco, 2mm**  
Finish



## DETAIL C



### Wood frame construction

- Balcony-bearing construction
- Custom element
- Finished with Derako demountable wood facade system

### Wooden Interface construction

- Custom wooden construction
- Connects custom balcony construction to building system standard beam
- Constructed on-site

### Terrace finish, wooden deck, 18mm

### Wood frame, 100 + 40mm

- Constructive element
- Lower frame aligned with insulation height gradient to allow water drainage

### Waterproof membrane

### Thermal Insulation (EPS), 250mm

- 10/1000 height gradient to facilitate water drainage

- Water drainage integrated in layer


### Vapor barrier

### Glu-lam 9m System beam

- Standard system element
- Thicker Variant compared to beams that do not bear balcony load



# DETAIL D



Terrace finish, wooden deck, 18mm

Wood frame, 100 + 40mm

Constructive element

opening at facade side to allow water to flow to  
drainage points

Waterproof membrane

Thermal Insulation (EPS), 250mm

10/1000 height gradient to facilitate water  
drainage

Water drainage integrated in layer

Seperate closed-off water drainage for green roof  
segments


Vapor barrier

Downspout coupling point

Downspout is integrated in pre-fab facade  
elements, extended to roof/terrace on-site




DETAIL E



- Extra large custom floor edge closer**  
Constructed with simple wood frame construction.  
Custom measurements to accommodate floor level difference.  
Space for pipes and cables.
- Floor level difference**  
Facilitates level transition between dwellings and roof terrace  
See Detail E'
- Custom ceiling add-on**  
Placed at the level difference, bottom floor elements have special custom ceiling add-ons (Fire protection, sound insulation) that provide full encapsulation of constructive elements.


DETAIL E'



- Standard Glu-Lam Post**  
450x450x3200 mm  
Integrated tubular steel interfaces at top and bottom side to connect elements.
- Custom Post-Beam Steel Interface**  
Executed as a single element with two different height levels for beams.  
Slid over topside of post interfaces before new constructive layer is added.
- Custom Post-Floor Steel Interface**  
Executed as a single element with two different height levels for floors.  
Attached to post interface
- Standard Glu-Lam Beams**  
(<)9000 mm span, 500 mm height (450+50)  
Attached to steel interfaces with 6 remountable bolts.




DETAIL F



- Floor Finish, 10mm**  
Variable material
- Dry floor heating screed, 35 mm**  
Easily disassemblable
- Insulating Foam, 40 mm**  
To optimize underfloor heating
- Hardboard, 18mm**  
Top layer of Pre-fab floor elements  
Pre-drilled holes with grid of 150 mm x 150 mm that allow easily disassemblable connections
- Honeycomb cardboard + Infill, 100mm**  
Additional constructive weight  
Sound insulation  
Height padding
- CLT Slab, 35+220+35 mm**  
Dwelling variant  
35 mm extra material on top and bottom as utility layers  
Top: Pre-drilled holes with grid of 150 mm x 150 mm that  
Bottom: Milled grooves to allow slide-on ceiling add-ons
- Ceiling Add-on - Frame, 50 mm**  
Wood frame attached to aluminium frames
- Ceiling Add-on - Rockwool, 40 mm**  
Additional sound insulation
- Ceiling Add-on - Gypsum Fibre Board Double layer, 30 mm**  
Fire protection  
Functional finishing layer (drilling small holes in ceiling, walls without damaging core element)
- Stucco**  
Finish



**DETAIL G**



- GFRP 3x 12,5 mm  
Outer layer used as functional finish layer
- Studs / Rockwool, 80m  
Sound insulation
- GFRP 3x 12,5 mm  
Rockwool 20 mm  
Decoupling layer  
Sound insulation
- GFRP 3x 12,5 mm  
Studs / Rockwool, 80m  
Sound insulation
- GFRP 3x 12,5 mm

**Interior wall connecting foot**  
Thin steel plate integrated on the bottom of pre-fab interior wall elements. Connects to pre-fab floor via disposable wooden interface

**Elastomer Joint**  
Decoupling element between wall and floor

**Interior wall wooden footprint / interface**  
Custom-measured wooden footprint that forms the disposable / non-reusable connecting element between system wall and system floor elements. Attached to floor via steel friction-fit pins. Attached to wall via simple screws.

**Steel pins**  
Friction-fit / demountable connection between wooden footprint and floor element. Goes through infill layer into CLT floor element.



FACADE FRAGMENT




Greenhouse

Dwellings

Discount  
store

Dwelling storage /  
retail / restaurant



HP +34.900

F9 +30.400

F8 +27.200

F4 +14.400

F3 +11.200

F2 +8.000

F1 +4.000

7


6.000

8



# SYSTEM GUIDE AND DETAILING





**MAIN CONCEPT: ATTACHMENT POINTS & INTERFACES**

The concept that forms the backbone of the whole system is the use of integrated attachment points in all elements, using steel interfaces to connect different elements together. Elements have both primary attachment points -meant for constructive connections -, and secondary attachment points - meant to connect with functional elements such as finishing layers, inner walls or installations. Primary attachment points are made of steel elements secured to the wooden bodies, while the secondary attachment points are mostly integrated into the wood via milling or drilling (holes, slits).

This concept gives the system the enormous flexibility that it needs for achieving universal reusability, as well as forming an easy basis to combine system elements with custom architecture. Finally, it also ensures that the system can develop over time without making older elements lose value - they can always be used in conjunction with newer elements by simply using the right interfaces.


**MAIN AND SECONDARY GRIDS**

The main constructional elements all follow a set horizontal grid of 1,5 by 1,5 meters. Primary attachment points are integrated into the elements where the grid lines intersect.





Vertically, there is no grid but instead a set of standard measurements that make the most sense in practice. In the example projects, the standard measurements of 3.200 (standard dwelling height) and 4.000 (standard commercial height) are used.

Some elements use their own inherent grids for secondary attachment points- most notably the floor elements and facade components. These grids are separate from the main grid and used mainly to give a consistent ground to attach elements such as inner walls, installations or finishing layers.












### DIVERSITY OF STRUCTURE AND SPACE

With the inherent flexibility of the interfaces and the combination of wall elements, columns and beams, a large variety of different structures and spaces can be made using the building system.

Depicted are a typical row house structure, an office building with double height plinth and a custom curved glass facade, a hexagon-shaped building with colosseum-like custom facade, and a simple structure for a large event hall.





# COLUMN ELEMENT

A

## VARIABLES

The column elements have two different variables. The first variable is the dimensions of the section, in the shown case 400 x 400. Standard models are available in steps of 100 mm .

The second variable is the height, which also varies according to a number of standard measurements, in this case based on the standard floor height of 3.200. The total height is this number increased by 400, as the columns slid inside of each other.

B

## PRIMARY ATTACHMENT POINTS

Steel elements form the primary attachment points at both extremes of the columns.

C

## SECONDARY ATTACHMENT POINTS

Each columns has slits milled into the wood at the corners to facilitate the de-mountable attachment of a finishing layer.




Holes drilled at a regular interval serve to pin the attachment in place vertically with friction fit metal pins.

D

## VARIANTS

The column elements vary according to several factors. Height, sectional dimensions, and shape.





# WALL ELEMENT

- A**

**VARIABLES**

The wall elements have three different variables. The first variable is the width, which is variable according to the standard Grid (V-G).

The second variant is the thickness, which varies according to a set of standard options (V-S).

The last variable is the height, which also varies according to a set of standard options (V-S). The standard used for dwelling type buildings is 3.200
- B**

**PRIMARY ATTACHMENT POINTS**

Steel attachment points are attached to the CLT body at a regular interval of 1.500 (Grid Unit). These steel elements are attached using multiple long screws. They serve as the backbone for the system, as they allow elements to be connected to theoretically any other element, using a variety of standard or custom interfaces.


At the bottom side they are only located at the corner, meant to secure the wall element itself. On the top side, they are placed at every grid unit to facilitate attachment to beams, floors or facade elements.

- C**



**VARIANTS**

Depicted are several variants of wall elements, including a custom variant with a custom shape milled out. Elements like these can be easily re-manufactured into standard elements reducing its size.









# BEAM ELEMENT

A

## VARIABLES

The beam elements have three variables. The first variable is the span, which varies in increments of the standard 1.500 mm grid unit.

The second variable is the thickness, which varies according to a number of standard measurements, based on the load the beam needs to bear.

The third variable is the height, which varies according to a number of a standard measurements, based on both the required load and the

B

## PRIMARY ATTACHMENT POINTS

Steel attachment points are attached to the CLT body at a regular interval of 1.500 (Grid Unit). These steel elements are attached using multiple long screws. They serve as the backbone for the system, as they allow elements to be connected to theoretically any other element, using a variety of standard or custom interfaces.

C

## SECONDARY ATTACHMENT POINTS

The bottom fo the beam elements have a layer of 50 mm non-loadbearing Glu-Lam, with slits milled to serve as attachment points for ceiling add-ons.

These addons are slid on the bottom of the beams and secured in place horizontally with friction fit steel pins placed in pre-drilled holes in the side.

D

## PRIMARY ATTACHMENT POINTS

At both extremes the beams have eight pre-drilled holes as well as a vertical slit milled into the Glu-Lam.


A variety of steel interfaces can be attached to this part of the beam, to attach it to different elements such as walls, columns or even other beams.

E



## VARIANTS

A depiction of several variants of beams, varying in span, height and thickness.









# FLOOR ELEMENT

A

## VARIABLES

The floor elements have three variables. The first variable is the span, which varies according to standard grid units of 1500 mm (V-G).

The second variable is the width, which also varies according to V-G.

The third variable is the thickness, which varies according to a number of standard measurements (V-S) based on both span and load. In this case the thickness is 220+50, with 220 mm of the thickness being load-bearing and the bottom 50 mm facilitating attachment points.

B

## PRIMARY ATTACHMENT POINTS

At the bottom side, each corner has milled-in space where the steel interfaces are placed to connect the floors to walls or beams.

These interfaces can vary in height to either heighten or lower the floor elements as required for the design.

C

## SECONDARY ATTACHMENT POINTS

Similar to the beam elements, the floor elements have a bottom layer of 50 mm non-loadbearing CLT with milled-in slits and pre-drilled holes.

These serve as attachment points for add-ons that can fulfill a variety and multiplicity of functions: sound insulation, fire proofing, electrics, ventilation and lowered ceiling (additional height).

D

## SECONDARY ATTACHMENT POINTS

On the top side, the floor elements have pre-drilled holes according to a simple grid of 150 x 150 mm.

These holes serve as the attachment points for both floor add-ons (extra height, sound insulation, weight) and the 'footprints' of walls.

These elements are connected via friction-fit steel pins to be completely remountable.

E

## VARIANTS

Depicted a several variants of the floor element, differing in width and span.

Notable is the bottom variant, which has double width and spacing in the middle for columns in the system grid. This variant makes use of the property of CLT where it can bear loads in both perpendicular directions, and only needs to be secured at the corners.



A

**Topside Add-on (PRE-FAB)**

Additional Height, Weight, Sound insulation. Variable according to building needs. Pre-drilled holes as attachment points for wall foot-prints.

B

**Floor Element (PRE-FAB)**

According to blueprint.

C



**Bottomside Add-on (PRE-FAB)**

Additional height, sound insulation, electrics and installations. Slid unto the bottom of the floor element and secured with horizontal friction fit pins.

D

**Ceiling Finish**



Fire-proofing. Finish. Added on-site. Variable.







# FACADE ELEMENTS

A



B



A

Facade elements are composed of standardized wooden milled elements with a grid of 100 mm. The main horizontal and vertical elements are demountable and reusable without any damage. Disposable lats are used to secure elements such as interfaces or Finish lats in non-reusable manner (screws).


The main elements have pre-drilled holes in a simple grid to allow the attachment of window and door frames in a demountable way via pins.

B


The elements can be configured in an almost infinite number of ways to facilitate rectangular facade openings of almost any size. Window and door frames are attached in a remountable way but are themselves disposable - windows and doors are attached to these frames with regular attachment methods such as screws.




C



D



E



C

A standard frame with lats attached.

D

Insulation, windows and foils (dampopen and waterproofing respectively on the interior and exterior sides) are added. Insulation is naturally demountable and reusable.


E

Finish lats are added on both the exterior and interior sides. Finishing layers are attached to these on-site with regular attachment methods such as screws. The lats are disposed after lifecycles.


Horizontal steel interfaces are added at the top and bottom sides of the interior to facilitate attachment of the facade elements to floors, beams and walls.



F



G



F

At this stage the elements are ready to be transported to the building site and attached to the main structure. In this case they are attached to interfaces on standard floor elements. Gaps and foils are sealed off with sealing tape on both the exterior and interior. The elements are designed to reserve space for this.

G

As the last step, finishing layers are added on the interior and exterior sides. Because the Finish lats are disposable, in principle anything can be attached to these elements as finishing layer, as long as the lats can bear its load. In the two example projects, existing remountable systems for wooden planks and a ceramic facade are used.

After the building life cycle has ended, the finishing layers (interior and exterior) can be removed, and the element can be dismantled as a whole. It can then be either directly reused as is in a similar design or transported to the factory to be reconfigured in a new shape.